

RETAINING WALL SUMMARY

PAYCODE #	ITEMS:	UNITS	STRUCTURE NUMBERS				TOTAL QTY.
			071-7003 WALL D	071-7004 WALL E	071-7005 WALL F	071-7006 WALL G	
50200100	Structure Excavation	CU YD	1128	3478	1997.5	291.3	6895
51500100	Name Plates	EACH	1	1	1	1	4
60109580	Pipe Underdrains for Structures, 4"	FOOT	659	1359	1089.8	349	3457
60602600	Concrete Gutter, Type A Modified	FOOT	658.7	1359	1089.8	349	3457
51202210	Furnishing Soldier Piles (HP Section)	FOOT			3269	649	3918
51202230	Furnishing Soldier Piles (W Section)	FOOT	1655	6501	1601		9757
51205200	Temporary Sheet Piling	SQ FT			38036		38036
59100100	Geocomposite Wall Drain	SQ YD	900	2358	1133	299	4690
Z0073002	Temporary Soil Retention System	SQ FT		4645			4645
X0324455	Drilling & Setting Soldier Piles (In Soil)	CU FT	1503	6156	7092	491	15242
X0324456	Drilling & Setting Soldier Piles (In Rock)	CU FT	3834	12436		1099	17369
X0325751	Driving Soldier Piles	FOOT			3269		3269
XZ127902	Retaining Wall (Special)	SQ FT	8881	22994	11721	3170	46766
	Staining Concrete Structures	SQ YD	800	2196	983	292	4271

FILE NAME =	USER NAME = cushmanbx	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	RETAINING WALL SUMMARY	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
or\pwork\pwork\cushmanbx\dms31213\08080808.dgn	DRAWN -	REVISED -	742			37R-4	OGLE	867	199	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 64E17			ILLINOIS FED. AID PROJECT				
PLOT DATE = Wed Mar 31 09:26:27 2010	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.			