

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

PANEL SIZE TABLE

PANEL	NOMINAL SIZE	NO.	SF PANELS
A	2 x 10	0	0
B	1.5 x 10 (sloped)	0	0
C	3 x 10	0	0
D	3 x 5	373	5595
E	2 x 5	65	650
F	1.5 x 5 (sloped)	3	23
G	1.5 x 5 (sloped)	0	0
H	1.5 x 10 (sloped)	0	0
I	3 x 10 (sloped)	0	0
J	3.5 x 10 (sloped)	0	0
Sheet 10 Total		441	6268

For actual Panel sizes, Reinforcement, and Finish see sheet 13 of 23.

See sheet 14 of 23 for drilled pile details

1358'-3<sup>5</sup>/<sub>8</sub>"

777'-8"

Panel Identifier. See Table Above for Nominal Dimension and Sheet 13 of 23 for Panel Details.

Elev. 701.82

Elev. 702.82

Elev. 699.82

Elev. 700.82

Elev. 680.82

MATCHLINE STA. 733+00

MATCHLINE STA. 736+00

156 Spa. @ Abt. 4'-11<sup>7</sup>/<sub>8</sub>" = 777'-8"

W21x132, Pile Tip Elev. = 668.49  
3'-0"  $\phi$  Pile Encasement

W21x166, Pile Tip Elev. = 667.99  
3'-0"  $\phi$  Pile Encasement

WALL PLAN

WALL PLAN  
STRUCTURE NO. 071-7004

DESIGNED	JMW
CHECKED	DFM
DRAWN	CTH
CHECKED	DFM

SHEET NO. 10	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
23 SHEETS	742	37R-4	OGLE	867	222
			CONTRACT NO. 64E17		
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT					