

GENERAL NOTES
(Revised May 13, 2009)

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS MICROSURFACING LIFTS.

SHORT TERM PAVEMENT MARKING SHALL BE USED TO OUTLINE EXIT AND ENTRANCE RAMPS FOR THE PRIME COAT APPLICATION AND EACH RESURFACING LIFT.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

BITUMINOUS MATERIALS (PRIME COAT)	0.08	GAL / SQ YD
SHORT TERM PAVEMENT MARKING	10	FT /100 FT OF APPLICATION
MIX FOR CRACKS, JTS & FLGWYS	0.00135	TONS / SQ YD
MICRO-SURFACING, SINGLE-PASS*	20	POUNDS/SQ YD

* MUST MEET FRICTION AGGREGATE REQUIREMENTS FOR MIXTURE D

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

CODE NO	ITEM	UNIT	TOTAL QTY	100% STATE
				CONST. CODE
				RDWY F000
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3910	3910
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	132	132
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	8
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	53317	53317
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	161568	161568
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	40392	40392
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2000	2000
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17594	17594
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	161568	161568
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	2000	2000
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	835	835
X0326221	MICRO-SURFACING, SINGLE PASS, TYPE II	SQ YD	49319	49319
* X0326725	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 6"	FOOT	40392	40392
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	60	60
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	LSUM	1	1
X0326867	RADAR SPEED TRAILER	CAL MO	1	1
X0326707	PORTABLE VEHICLE MOUNTED CHANGEABLE MESSAGE SIGN	CAL MO	1	1

*SPECIALTY ITEMS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: Don Bevilacqua
DISTRICT STUDIES & PLANS ENGINEER

DATE: 3/30/10

EXAMINED BY: Robert J. ...
DISTRICT CONSTRUCTION ENGINEER

...
DISTRICT MATERIALS ENGINEER

...
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = braboypc	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES AND SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\PIV\DOT\BRABOYPC\0180748\4366a16-shr-cover.dgn		DRAWN -	REVISED -			80	(06)-3,4RS-3; 5,6RS-2	BUREAU	6	2	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 66A16					
PLOT DATE = Mar 30, 2010 - 08:48:30 AM		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____