

SUMMARY OF QUANTITIES				100% STATE	100% STATE	100% STATE	
FUND CODE TYPE:				L01E	07A0	L01E	L01E
CONSTRUCTION CODE TYPE:				I000	I000	X271-2A	X171-2A
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY	BRIDGE SN 006-0020 SN 006-0021	BRIDGE SN 006-0022 SN 006-0023
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3853	3853			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9			
40600745	POLYMERIZED LEVELING BINDER (HAND METHOD), N90	TON	15	15			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	2514	2514			
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3083	2849		98	136
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2777			1164	1613
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	7990	7990			
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	19951	19951			
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	600	600			
44201019	CLASS B PATCHES, TYPE II, 14 INCH	SQ YD	200		200		
44201023	CLASS B PATCHES, TYPE III, 14 INCH	SQ YD	52		52		
44201025	CLASS B PATCHES, TYPE IV, 14 INCH	SQ YD	473		473		
X4420114	CLASS B PATCHES, TYPE II, 14 INCH, SPECIAL	SQ YD	298		298		
X4421025	CLASS B PATCHES, TYPE IV, 14 INCH, SPECIAL	SQ YD	93		93		
44213100	PAVEMENT FABRIC	SQ YD	1235		1235		
44213200	SAW CUTS	FOOT	4340		4340		
48203017	HOT-MIX ASPHALT SHOULDERS, 5"	SQ YD	600	600			
67100100	MOBILIZATION	L SUM	1	1			
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	8			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	14	14			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1410	1410			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	465	465			
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	183778	183058	720		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	176	176			
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	25	25			
* X0326725	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 6"	FOOT	3728	3524	204		
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	LSUM	1	1			
Z0017202	DOWEL BARS 1 1/2"	EACH	1480		1480		
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	80			40	40
Z0075310	TIE BARS 3/4"	EACH	212		212		
X0326867	RADAR SPEED TRAILER	CAL MO	1	1			
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	1	1			

\* SPECIALTY ITEMS

DESIGNED - RON WOODSHANK	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE. 80	SECTION •	COUNTY	TOTAL SHEETS 12	SHEET NO. 3
DRAWN - RON WOODSHANK	REVISED -			BUREAU		CONTRACT NO. 66A33		
CHECKED -	REVISED -			ILLINOIS				
DATE -	REVISED -	SCALE: _____	SHEET NO. 1 OF 1 SHEETS	STA. _____	TO STA. _____			