

PAVEMENT MARKING SCHEDULE - IL RTE. 17					
LOCATION L.M. - L.M.	PAINT PAVEMENT MARKING LINE 4''		PAINT PAVEMENT MARKING LINE 6''		REMARKS
	FOOT		FOOT		
	YELLOW	WHITE	YELLOW		
L.M. 0.00					IL RTE. 47
0.00 - 1.50	264	15840	1980		IL RTE. 47 TO ASHLEY RD.
L.M. 1.50					ASHLEY RD.
1.50 - 2.53		10877	1360		ASHLEY RD. TO CHURCH RD.
L.M. 2.53					CHURCH RD.
2.53 - 3.54		10666	1333		CHURCH RD. TO BRISBIN RD.
L.M. 3.54					BRISBIN RD.
3.54 - 4.35		8554	1069		BRISBIN RD. TO GROVE RD. (CH 2)
L.M. 4.35					GROVE RD. (CH 2)
4.35 - 5.33		10349	1294		GROVE RD. (CH 2) TO OBRIEN RD
L.M. 5.33					OBRIEN RD
5.33 - 5.59		2746	343		OBRIEN RD. TO McKANNA RD.
L.M. 5.59					McKANNA RD.
5.59 - 6.81		12883	1610		McKANNA RD. TO JUGHANDLE RD.
L.M. 6.81					JUGHANDLE RD.
6.81 - 7.32		5386	673		JUGHANDLE RD. TO ARBEITER RD.
L.M. 7.32					ARBEITER RD.
7.32 - 8.32		10560	1320		ARBEITER RD. TO N. RIDGE RD. (CR 11)
L.M. 8.32					RIDGE RD. (CR 11)
8.32 - 9.31	4964	10454	1307		N. RIDGE RD. (CR 11) TO COUNTY LINE RD (Will CO. LN.)
L.M. 9.31					COUNTY LINE RD (Will CO. LN.)
SUBTOTAL	5228	98315	12289		
TOTAL	103543		12289		

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RON WOODSHANK	REVISED -
c:\pwwork\PWDOT\WOODSHANKRL\d0189879	D366A45details.dgn	DRAWN - RON WOODSHANK	REVISED -
	PLOT SCALE = 100.0000 / IN.	CHECKED -	REVISED -
	PLOT DATE = Apr 26, 2010 - 09:47:16 AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: _____	SHEET NO. 1 OF 1 SHEETS	STA. _____ TO STA. _____
--------------	-------------------------	--------------------------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	D3 CRACK SEAL 2011-4	KENDALL	7	6
CONTRACT NO. 66A45			ILLINOIS FED. AID PROJECT	