

GENERAL NOTES

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

| SUMMARY OF QUANTITIES | | | |
|-----------------------|--|-------------------------|----------------|
| CODE NO. | ITEM | CONSTRUCTION CODE TYPE: | Y004 |
| | | UNIT | TOTAL QUANTITY |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 779 |
| 25000200 | SEEDING, CLASS 2 | ACRE | 0.16 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 14 |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 14 |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 14 |
| 25100115 | MULCH, METHOD 2 | ACRE | 0.16 |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 16 |
| 67100100 | MOBILIZATION | L SUM | 1 |
| Z0007601 | BUILDING REMOVAL NO. 1 | L SUM | 1 |
| Z0007602 | BUILDING REMOVAL NO. 2 | L SUM | 1 |
| * Z0049901 | REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1 | L SUM | 1 |

* SPECIALTY ITEMS

| TOPSOIL & SEEDING | | | | | | |
|----------------------------|------------------------------|-----------------|------------------------------|--------------------------------|-------------------------------|----------------|
| BUILDING NUMBER (PARCEL #) | TOPSOIL FURNISH AND PLACE 4" | SEEDING CLASS 2 | NITROGEN FERTILIZER NUTRIENT | PHOSPHORUS FERTILIZER NUTRIENT | POTASSIUM FERTILIZER NUTRIENT | MULCH METHOD 2 |
| | SQ YD | ACRE | TON | TON | TON | ACRE |
| 1 (3JT0001) | 344 | 0.07 | 6 | 6 | 6 | 0.07 |
| 2 (3JT0003) | 435 | 0.09 | 8 | 8 | 8 | 0.09 |
| TOTALS | 779 | 0.16 | 14 | 14 | 14 | 0.16 |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: *David P. ...*
ACTING DISTRICT STUDIES & PLANS ENGINEER

DATE: May 17, 2010

EXAMINED BY: *Herbert ...*
DISTRICT CONSTRUCTION ENGINEER

...
DISTRICT MATERIALS ENGINEER

...
DISTRICT OPERATIONS ENGINEER