

SCHEDULE
COMBINATION CURB AND GUTTER REMOVAL

LOCATION	QUANTITY
	FOOT
STA. 9+00.85 (IL. 121) TO STA. 56+35 (IL. 10) RT.	150
STA. 6+82 (IL. 121) TO STA. 57+08 (IL. 10) LT.	260
TOTAL	410

SCHEDULE
PORTLAND CEMENT CONCRETE SIDEWALK 4"

LOCATION	QUANTITY
	SQ. FT.
STA. 6+77 (IL. 121) TO STA. 56+61 LT.	916
STA. 8+90.85 (IL. 121) TO STA. 57+22 (IL. 10) RT.	1070
TOTAL	1986

SCHEDULE
PIPE CULVERTS, CLASS A, TYPE 1, RCCP 12"

LOCATION	QUANTITY
	FOOT
STA. 55+55 14' LT. TO STA. 55+61 39' LT.	26
TOTAL	26

SCHEDULE
STORM SEWERS, CLASS A, TYPE 1, 15"

LOCATION	QUANTITY
	FOOT
STA. 55+88 43.4' RT. TO STA. 56+05 60.2' RT.	24
STA. 56+05 60.2' RT. TO STA. 57+10 31.2 RT.	108
TOTAL	132

SCHEDULE
STORM SEWER REMOVAL

LOCATION	QUANTITY
	FOOT
STA. 55+47 16' LT. TO 36' LT.	20
TOTAL	20

SCHEDULE
COMBINATION CONCRETE CURB AND GUTTER, TYPE B 6.18

LOCATION	QUANTITY
	FOOT
STA. 9+01 (IL. 121) TO STA. 57+80.5 (IL. 10) RT.	267
STA. 6+82 (IL. 121) TO STA. 57+80.5 (IL. 10) LT.	331
TOTAL	598

SCHEDULE
DETECTABLE WARNINGS

LOCATION	QUANTITY
	SQ. FT.
STA. 55+43 20' LT.	10
STA. 55+82 55' RT.	10
TOTAL	20

SCHEDULE
SUB-BASE GRANULAR MATERIAL, TYPE A 6"

LOCATION	QUANTITY
	SQ. YD.
STA. 9+00.85 (IL. 121) TO STA. 57+80.5 RT. (IL. 10)	70
STA. 55+26 TO STA. 57+27.38 RT. (PAVEMENT)	212
STA. 55+26 TO STA. 56+36.81 LT. (PAVEMENT)	11
STA. 6+82 (IL. 121) TO STA. 57+80.5 (IL. 10) LT.	90
TOTAL	383

SCHEDULE
MEDIAN SURFACE REMOVAL

LOCATION	QUANTITY
	SQ. FT.
STA. 2+08.5 TO STA. 3+52	731
STA. 11+33.5 TO STA. 13+04	775
STA. 47+52 TO STA. 48+06	237
STA. 56+85 TO STA. 57+47	255
TOTAL	1998

SCHEDULE
TRENCH BACKFILL

LOCATION	QUANTITY
	CU. YD.
STA. 55+73 TO STA. 56+05 RT. (IL. 10)	4
STA. 56+05 TO STA. 57+10 RT. (IL. 10)	23
STA. 55+55 TO STA. 55+61 LT. (IL. 10)	5
TOTAL	32

SCHEDULE
PORTLAND CEMENT CONCRETE BASE COURSE 9"

LOCATION	QUANTITY
	SQ. YD.
STA. 55+26 TO STA. 57+27.38 RT.	212
STA. 55+26 TO STA. 56+36.81 LT.	12
MEDIAN AREAS	222
TOTAL	446

SCHEDULE
SIDEWALK REMOVAL

LOCATION	QUANTITY
	SQ. FT.
STA. 55+66 TO STA. 57+22 RT.	500
STA. 6+77 (IL. 121) TO STA. 56+61 (IL. 10) LT.	1117
TOTAL	1617

SCHEDULE
PRECAST REINFORCED CONCRETE END SECTIONS 12"

LOCATION	QUANTITY
	SQ. FT.
STA. 55+61 39' LT.	1
TOTAL	1

SCHEDULE
ESTIMATED QUANTITIES FOR COMBINATION
CURB AND GUTTER REMOVAL AND REPLACEMENT
& MEDIAN SURFACE REMOVAL AND REPLACEMENT

LOCATION	COMB. CURB & GUTTER REMOVAL & REPLACEMENT	MEDIAN SURFACE REMOVAL & REPLACEMENT
	FOOT	SQ. FT.
ENTIRE PROJECT ESTIMATE	1144	1260
TOTAL	1144	1260

SCHEDULE
PAVEMENT PATCHING TYPE III. 14"

LOCATION	QUANTITY
	SQ. YD.
STA. 2+09, BOTH LANES, 1 PATCH @ 23 SQ. YD. & 1 PATCH @ 20 SQ. YD.	43
STA. 11+60, BOTH LANES, 2 PATCHES @ 19 SQ. YD. EACH	38
TOTAL	81

SCHEDULE
CLASS C PATCHES, TYPE III. 14"

LOCATION	QUANTITY
	SQ. YD.
SOUTHBOUND STA. 57+58, BOTH LANES, 2 PATCHES @ 20 SQ. YD. EACH	40
NORTHBOUND STA. 57+58, BOTH LANES, 2 PATCHES @ 20 SQ. YD. EACH	40
TOTAL	80

SCHEDULE
AGGREGATE WEDGE SHOULDER, TYPE B

LOCATION	QUANTITY
	TON
STA. 50+54+ TO STA. 57+50 (EAST SIDE)	16.5
STA. 50+59 TO STA. 57+50 (WEST SIDE)	16.5
TOTAL	33

SCHEDULE
WATER VALVES TO BE ADJUSTED

LOCATION	QUANTITY
	EACH
STA. 52+29, 22' LT.	1
STA. 52+40, 56' LT.	1
STA. 55+69, 10' LT.	1
STA. 56+12, 12' RT.	1
STA. 56+12, 28' LT.	1
STA. 60+01, 34' RT.	1
STA. 60+11, 11' LT.	1
STA. 39+06, 16' RT.	1
STA. 41+42, 17' RT.	1
TOTAL	9

SCHEDULE
MANHOLES TO BE ADJUSTED

LOCATION	QUANTITY
	EACH
STA. 52+09, 26' RT.	1
STA. 52+16, 2' RT.	1
STA. 52+69, 25' RT.	1
STA. 55+53, 21' RT.	1
STA. 56+02, 2' RT.	1
STA. 57+60, 15' RT.	1
STA. 59+31, 18' RT.	1
STA. 59+82, 1' RT.	1
STA. 60+30, 15' RT.	1
STA. 0+05, 18' RT.	1
STA. 1+68, 26' RT.	1
STA. 26+38, 27' RT.	1
STA. 30+34, 5' RT.	1
STA. 36+04, 1' RT.	1
STA. 39+25, 15' RT.	1
STA. 39+53, 6' RT.	1
STA. 40+55, 9' RT.	1
STA. 42+78, 7' RT.	1
STA. 43+13, 10' LT.	1
STA. 46+36, 11' LT.	1
STA. 46+54, 3' RT.	1
STA. 49+82, C	1
STA. 50+38, 16' LT.	1
TOTAL	23

FILE NAME = c:\pwwork\pww007\LAUGHLIN\RL\d0181122\d072998-ah-t-schedule.dgn
 USER NAME = laughlinr1
 PLOT SCALE = 2.0000' / IN.
 PLOT DATE = Mar-18-2018 @2:16:40PM

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -



Allen Henderson & Associates, Inc.
 Civil and Structural Engineers Springfield, IL
 62703 Phone: (217)544-8033 IL Design Firm
 No. 184-001907

QUANTITY SCHEDULES

SCALE: SHEET NO. 9 OF 32 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71T	(242)RS-4(116 RS-5	LOGAN	32	9

CONTRACT NO. 72998
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT