

**WORK ZONE PAVEMENT MARKING REMOVAL**  
(TEMPORARY PAVEMENT MARKING NOT INCLUDED)

LOCATION	SQ FT
<b>EAI-72</b> (SCOTT COUNTY)	1230
(MORGAN COUNTY)	1573
<b>BL-72/US_67</b>	705
TOTAL = 3508	

**TEMPORARY CONCRETE BARRIER**

LOCATION	FOOT
<b>EAI-72</b> (SCOTT COUNTY)	
STAGE I, (SN 086-0023/24)	
RT. STA. 197+05.5 TO RT. STA. 200+31	325
LT. STA. 199+70 TO LT. STA. 202+94.5	325
TOTAL = 650	

**RELOCATE TEMPORARY CONCRETE BARRIER**

LOCATION	FOOT
<b>EAI-72</b> (SCOTT COUNTY)	
STAGE II, (SN 086-0023/24)	
RT. STA. 197+06.5 TO RT. STA. 200+31	325
LT. STA. 199+70 TO LT. STA. 202+91.5	325
TOTAL = 650	

**PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"**

LOCATION	CENTERLINE SKIP-DASH WHITE FOOT
<b>EAI-72</b> (SCOTT COUNTY)	
WB STA. 107+16.06 TO STA. 199+17.81	2300
EB STA. 106+86.47 TO STA. 198+64.60	2294
WB STA. 201+33.78 TO STA. 262+29.22	1524
EB STA. 200+82.53 TO STA. 262+29.22	1537
(MORGAN COUNTY)	
WB STA. 262+29.22 TO STA. 443+19.48	4522
EB STA. 262+29.22 TO STA. 443+19.48	4522
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH	
WB STA. 10+03.94 TO STA. 22+74.37	318
EB STA. 10+03.94 TO STA. 26+47.25	411
<b>BL-72/US_67</b>	
NB STA. 356+25 TO STA. 453+98	2443
SB STA. 372+50 TO STA. 449+60	1927
TOTAL = 21,798	

**RAISED REFLECTIVE PAVEMENT MARKER**

LOCATION	EACH
<b>EAI-72</b> (SCOTT COUNTY)	
WB STA. 107+16.06 TO STA. 199+17.81	115
EB STA. 106+86.47 TO STA. 198+64.60	115
WB STA. 201+33.78 TO STA. 262+29.22	76
EB STA. 200+82.53 TO STA. 262+29.22	77
(MORGAN COUNTY)	
WB STA. 262+29.22 TO STA. 443+19.48	226
EB STA. 262+29.22 TO STA. 443+19.48	226
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH	
WB STA. 10+03.94 TO STA. 22+74.37	16
EB STA. 10+03.94 TO STA. 26+47.25	21
<b>BL-72/US_67</b>	
NB STA. 356+25 TO STA. 453+98	244
SB STA. 372+50 TO STA. 449+60	192
TOTAL = 1308	

**GUARDRAIL MARKERS, TYPE A**

LOCATION	EACH
<b>BL-72/US_67</b> (MORGAN COUNTY)	
RT. STA. 322+75.71 TO RT. STA. 327+03.00	5
LT. STA. 325+98.00 TO LT. STA. 330+25.29	5
RT. STA. 400+42.71 TO RT. STA. 403+45.00	4
LT. STA. 403+75.00 TO LT. STA. 406+77.29	4
TOTAL = 18	

**BARRIER WALL MARKERS, TYPE C**

LOCATION	EACH
<b>EAI-72</b> (SCOTT COUNTY)	
STAGE I, (SN 086-0023/24)	
RT. STA. 197+05.5 TO RT. STA. 200+31	26
LT. STA. 199+70 TO LT. STA. 202+94.5	26
TOTAL = 52	

**TERMINAL MARKER-DIRECT APPLIED**

LOCATION	EACH
<b>BL-72/US_67</b> (MORGAN COUNTY)	
RT. STA. 322+75.71	1
LT. STA. 330+25.29	1
RT. STA. 400+42.71	1
LT. STA. 406+77.29	1
TOTAL = 4	

**PAVEMENT MARKING REMOVAL**

LOCATION	TYPE OF MARKING	SQ FT
<b>EAI-72</b> (SCOTT COUNTY)		
RT. STA. 190+84 TO RT. STA. 203+00 (EB)	SKIP-DASH	127
RT. STA. 195+82 TO RT. STA. 202+91 (EB)	LANE LINE (WHITE)	295
RT. STA. 195+84 TO RT. STA. 202+99 (EB)	LANE LINE (YELLOW)	298
LT. STA. 197+07 TO LT. STA. 209+16 (WB)	SKIP-DASH	126
LT. STA. 197+10 TO LT. STA. 204+16 (WB)	LANE LINE (WHITE)	294
LT. STA. 197+07 TO LT. STA. 204+14 (WB)	LANE LINE (YELLOW)	295
TOTAL = 1435		

**RAISED REFLECTIVE PAVEMENT MARKER REMOVAL**

LOCATION	EACH
<b>EAI-72</b> (SCOTT COUNTY)	
WB STA. 107+16.06 TO STA. 199+17.81	115
EB STA. 106+86.47 TO STA. 198+64.60	115
WB STA. 201+33.78 TO STA. 262+29.22	76
EB STA. 200+82.53 TO STA. 262+29.22	77
(MORGAN COUNTY)	
WB STA. 262+29.22 TO STA. 443+19.48	226
EB STA. 262+29.22 TO STA. 443+19.48	226
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH	
WB STA. 10+03.94 TO STA. 22+74.37	16
EB STA. 10+03.94 TO STA. 26+47.25	21
<b>BL-72/US_67</b>	
NB STA. 356+25 TO STA. 453+98	244
SB STA. 372+50 TO STA. 449+60	192
TOTAL = 1308	

**CLEANING UNDERDRAIN OUTLETS**

LOCATION	EACH
<b>EAI-72</b> (SCOTT COUNTY)	124
(MORGAN COUNTY)	158
<b>BL-72/US_67</b>	78
TOTAL = 360	

**OUTLET MARKER**

LOCATION	EACH
<b>EAI-72</b> (SCOTT COUNTY)	124
(MORGAN COUNTY)	158
<b>BL-72/US_67</b>	78
TOTAL = 360	

**MATERIAL TRANSFER DEVICE**

LOCATION	TON
<b>EAI-72</b> (SCOTT COUNTY)	17,318
(MORGAN COUNTY)	22,107
<b>BL-72/US_67</b>	9887
TOTAL = 49,312	

**BOLLARDS**

LOCATION	EACH	REMOVAL EACH
<b>EAI-72</b> (SCOTT COUNTY)		
STA. 113+60	5	5
STA. 137+95	5	2
STA. 142+80		2
STA. 145+75	5	3
STA. 151+25	5	3
STA. 180+00	5	4
STA. 213+10	5	3
STA. 221+40	5	
STA. 229+80	5	2
STA. 235+55	5	2
STA. 248+00	5	
(MORGAN COUNTY)		
STA. 274+00	5	1
STA. 287+00	5	
STA. 305+00	2	2
STA. 315+00	5	4
STA. 347+90	5	4
STA. 360+90	5	3
STA. 373+90	5	4
STA. 393+00		6
STA. 395+00		2
STA. 406+00	2	
STA. 414+00	2	
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH		
STA. 13+00	5	4
STA. 23+70	5	3
<b>BL-72/US_67</b>		
STA. 373+90	5	
STA. 393+90	5	
STA. 398+80	5	
STA. 410+30	5	
STA. 433+10	5	
STA. 452+90	5	
TOTALS =		59

**MAINTENANCE MOWING**

LOCATION	ACRE
<b>EAI-72</b> (SCOTT COUNTY)	
STA. 107+00 TO STA. 262+29.22	47
(MORGAN COUNTY)	
STA. 262+29.22 TO STA. 443+19.48	55
<b>BL-72/US_67</b>	
STA. 356+00 TO STA. 395+60	12
STA. 395+60 TO STA. 427+60	10
STA. 427+60 TO STA. 440+70	4
STA. 440+70 TO STA. 454+00	3
TOTAL = 131	

**GROOVING FOR RECESSED PAVEMENT MARKING 6"**

LOCATION	EDGELINE	
	SOLID WHITE FOOT	SOLID YELLOW FOOT
<b>EAI-72</b> (SCOTT COUNTY)		
WB STA. 107+16.06 TO STA. 199+17.81	9202	9202
EB STA. 106+86.47 TO STA. 198+64.60	9178	9178
WB STA. 201+33.78 TO STA. 262+29.22	6096	6096
EB STA. 200+82.53 TO STA. 262+29.22	6147	6147
(MORGAN COUNTY)		
WB STA. 262+29.22 TO STA. 443+19.48	18,090	18,090
EB STA. 262+29.22 TO STA. 443+19.48	18,090	18,090
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH		
WB STA. 10+03.94 TO STA. 22+74.37	1270	1270
EB STA. 10+03.94 TO STA. 26+47.25	1643	1643
<b>BL-72/US_67</b>		
NB STA. 356+25 TO STA. 453+98	9773	9773
SB STA. 372+50 TO STA. 449+60	7710	7710
SUB TOTALS =		87,199
TOTAL = 174,398		

• 86-10RS-3, 69-6RS-2, 69-1RS  
• SCOTT, MORGAN

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72			48	8
CONTRACT NO. 72A16				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
c:\pwwork\pwwork\LAUGHLINR1\dms24453\72A16-shr-schedule.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

