

SECTION "A" (OLD IL 29 / J. DAVID JONES / WALNUT) PATCHING								
CLASS B - 10" NORTH BOUND								
STATION	LOCATION	LENGTH	WIDTH	SAW CUTS	TY II, 10"	TY III, 10"	DOWEL BARS	PAVEMENT FABRIC
		(FT)	(FT)	(FT)	(SQ YD)	(SQ YD)	(EACH)	(SQ YD)
546+50	DL	6	12	48	8.00		20	8
546+50	PL	6	12	48	8.00		20	8
547+50	DL	12	12	60		16.00	20	16
547+50	PL	12	12	60		16.00	20	16
548+50	DL	6	12	48	8.00		20	8
548+50	PL	6	12	48	8.00		20	8
557+00	DL	15	12	66		20.00	20	20
566+50	PL	10	12	56	13.33		20	13
567+50	PL	6	12	48	8.00		20	8
568+50	PL	6	12	48	8.00		20	8
570+80	DL	6	12	48	8.00		20	8
570+80	PL	6	12	48	8.00		20	8
571+30	DL	15	12	66		20.00	20	20
571+30	PL	15	12	66		20.00	20	20
583+00	PL	6	12	48	8.00		20	8
583+50	PL	6	12	48	8.00		20	8
584+50	DL	6	12	48	8.00		20	8
584+50	PL	6	12	48	8.00		20	8
585+50	PL	6	12	48	8.00		20	8
586+50	DL	6	12	48	8.00		20	8
586+50	PL	6	12	48	8.00		20	8
587+50	DL	6	12	48	8.00		20	8
587+50	PL	6	12	48	8.00		20	8
598+50	DL	6	12	48	8.00		20	8
598+50	PL	6	12	48	8.00		20	8
599+50	DL	6	12	48	8.00		20	8
599+50	PL	6	12	48	8.00		20	8
TOTALS				1382	181	92	540	273

SECTION "A" (OLD IL 29 / J. DAVID JONES / WALNUT) PATCHING										
CLASS B - 10" SOUTH BOUND										
STATION	LOCATION	LENGTH	WIDTH	SAW CUTS	TIE BARS	TY II, 10"	TY III, 10"	TY IV, 10"	Dowel Bars	PAVT FABRIC
		(FT)	(FT)	(FT)	(EACH)	(SQ YD)	(SQ YD)	(SQ YD)	(EACH)	(SQ YD)
534+50	DL	16	12	68				21.33	20	21
534+50	PL	16	12	68				21.33	20	21
535+50	DL	15	12	66				20.00	20	20
535+50	PL	15	12	66				20.00	20	20
539+20	DL	6	12	48		8.00			20	8
539+20	PL	6	12	48		8.00			20	8
541+00	DL	12	12	60				16.00	20	16
541+00	PL	12	12	60				16.00	20	16
542+50	DL	10	12	56		13.33			20	13
542+50	PL	10	12	56		13.33			20	13
543+50	DL	6	12	48		8.00			20	8
544+50	DL	12	12	60				16.00	20	16
544+50	PL	12	12	60				16.00	20	16
545+50	PL	6	12	48		8.00			20	8
546+50	DL	6	12	48		8.00			20	8
546+50	PL	6	12	48		8.00			20	8
549+50	DL	30	12	96	15			40.00	20	40
549+50	PL	30	12	96	15			40.00	20	40
556+50	DL	20	12	76	10			26.67	20	27
556+50	PL	20	12	76	10			26.67	20	27
557+50	DL	14	12	64				18.67	20	19
557+50	PL	14	12	64				18.67	20	19
565+50	DL	12	12	60				16.00	20	16
565+50	PL	12	12	60				16.00	20	16
613+20	DL	17	12	70				22.67	20	23
613+20	PL	17	12	70				22.67	20	23
616+00	DL	14	12	64				18.67	20	19
616+00	PL	14	12	64				18.67	20	19
TOTALS				1768	50	75	299	133	560	507

FILE NAME =	USER NAME = laughl1nrl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et\pwork\PWIDOT\LAUGHLINRL\dms47710\0572C35-eh-t-schedule.dgn	DRAWN -	REVISED -	658					*	SANGAMON	206	10	
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 72C35									
PLOT DATE = Apr-30-2010 09:13:32AM	DATE -	REVISED -	SCALE:					SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	