

SECTION "A" (OLD IL 29 / J. DAVID JONES / WALNUT) PATCHING						
CLASS D - 12"						
NORTH BOUND						
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 12" (SQ YD)	TY III, 12" (SQ YD)	TY IV, 12" (SQ YD)
26+00	DL	10	11	12.22		
21+25	DL	6	11	7.33		
21+25	PL	6	11	7.33		
8+75	DL	25	11			30.56
8+75	PL	25	11			30.56
632+60	DL	5	11	6.11		
632+60	Parking Lane	5	9	5.00		
630+00	DL	20	11		24.44	
630+00	Parking Lane	20	9		20.00	
629+50	DL	5	11	6.11		
629+50	Parking Lane	5	9	5.00		
626+90	DL	6	11	7.33		
626+90	Parking Lane	6	9	6.00		
TOTALS				62	44	61
MEDIAN TURN LANE						
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 12" (SQ YD)		
21+25	MTL	6	11	7.33		
11+40	MTL	6	11	7.33		
TOTALS				15		
SOUTH BOUND						
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 12" (SQ YD)	TY III, 12" (SQ YD)	TY IV, 12" (SQ YD)
22+80	DL	15	11		18.33	
21+90	DL	50	11			61.11
21+25	DL	6	11	7.33		
21+25	PL	6	11	7.33		
11+40	DL	6	11	7.33		
11+40	PL	6	11	7.33		
632+60	DL	5	11	6.11		
632+60	Parking Lane	5	9	5.00		
626+90	DL	6	11	7.33		
626+90	Parking Lane	6	9	6.00		
TOTALS				54	18	61

SECTION "B" (IL 4 / VETERANS PKWY) PATCHING									
CLASS A - 8"									
SOUTH BOUND									
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	PATCH REINF. (SQ YD)	SAW CUTS (FT)	TIE BARS (EACH)	TY II, 8" (SQ YD)	TY IV, 8" (SQ YD)	
109+60	PL	20	12	26.67	76	10		26.67	
110+20	DL	10	12	13.33	56		13.33		
110+20	PL	30	12	40.00	96	15		40.00	
111+25	PL	20	12	26.67	76	10		26.67	
TOTALS				107	304	35	13	93	
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	PATCH REINF. (SQ YD)	SAW CUTS (FT)	TIE BARS (EACH)	TY II, 11" (SQ YD)	TY III, 11" (SQ YD)	TY IV, 11" (SQ YD)
103+00	NB LTL	8	12	10.67	52		10.67		
103+80	NB LTL	22	12	29.33	80	11			29.33
104+00	NB LTL	14	12	18.67	64			18.67	
104+70	NB DL	6	12	8.00	48		8.00		
106+30	NB PL	6	12	8.00	48		8.00		
TOTALS				74	292	11	27	19	29

FILE NAME =	USER NAME = loughlinc1	DESIGNED -	REVISED -
ca:\pwork\PWIDOT\LAUGHLINRL\dms47710\72C35-aht-schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Apr-30-2010 09:14:13AM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PATCHING SCHEDULES			
SCALE:	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.

F.A.P. RTE. 658	SECTION •	COUNTY SANGAMON	TOTAL SHEETS 206	SHEET NO. 11
CONTRACT NO. 72C35				
ILLINOIS FED. AID PROJECT				