

SECTION "B" (IL 4 / VETERANS PKWY) PATCHING					
NORTH BOUND			CLASS D		
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 14" (SQ YD)	TY III, 12" (SQ YD)
256+00	DL	6	12	8.00	
256+00	PL	6	12	8.00	
256+80	DL	6	12	8.00	
256+80	PL	6	12	8.00	
257+50	DL	6	12	8.00	
257+50	PL	6	12	8.00	
258+05	DL	6	12	8.00	
258+05	PL	6	12	8.00	
267+00	DL	6	12	8.00	
267+00	PL	6	12	8.00	
270+32	DL	6	12	8.00	
270+32	PL	6	12	8.00	
272+90	DL	10	12	13.33	
272+90	PL	10	12	13.33	
278+50	DL	10	12	13.33	
278+50	PL	10	12	13.33	
280+12	DL	6	12	8.00	
280+12	PL	6	12	8.00	
281+60	DL	10	12	13.33	
281+60	PL	10	12	13.33	
484+20	DL	6	12	8.00	
484+20	PL	6	12	8.00	
486+25	DL	17	12		22.67
486+25	PL	17	12		22.67
487+55	DL	6	12	8.00	
488+05	PL	18	12		24.00
488+35	DL	8	12	10.67	
491+15	DL	6	12	8.00	
491+15	PL	6	12	8.00	
491+90	DL	6	12	8.00	
491+90	PL	6	12	8.00	
496+00	DL	6	12	8.00	
496+00	PL	6	12	8.00	
496+00	LTL	6	12	8.00	
496+20	DL	6	12	8.00	
496+20	PL	6	12	8.00	
496+20	LTL	6	12	8.00	
TOTALS				307	69

SECTION "B" (IL 4 / VETERANS PKWY) PATCHING					
SOUTH BOUND			CLASS D		
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 14" (SQ YD)	TY III, 14" (SQ YD)
256+65	DL	6	12	8.00	
256+65	PL	6	12	8.00	
258+25	DL	6	12	8.00	
258+25	PL	6	12	8.00	
258+60	PL	6	12	8.00	
259+20	DL	6	12	8.00	
259+20	PL	6	12	8.00	
261+50	PL	6	12	8.00	
261+60	DL	6	12	8.00	
266+00	DL	6	12	8.00	
266+00	RTL	6	12	8.00	
270+05	DL	6	12	8.00	
270+80	DL	8	12	10.67	
270+80	PL	8	12	10.67	
271+65	DL	8	12	10.67	
271+65	PL	8	12	10.67	
272+25	DL	6	12	8.00	
278+65	DL	12	12		16.00
278+65	PL	8	12	10.67	
281+70	DL	6	12	8.00	
281+70	PL	6	12	8.00	
282+20	DL	6	12	8.00	
282+20	PL	6	12	8.00	
383+40	DL	6	12	8.00	
383+40	PL	6	12	8.00	
384+15	DL	8	12	10.67	
384+15	PL	8	12	10.67	
385+35	DL	15	12		20.00
385+35	PL	6	12	8.00	
386+90	DL	6	12	8.00	
386+90	PL	6	12	8.00	
391+00	DL	6	12	8.00	
391+00	PL	6	12	8.00	
392+50	DL	6	12	8.00	
393+30	DL	6	12	8.00	
393+70	DL	6	12	8.00	
393+70	PL	6	12	8.00	
394+65	DL	6	12	8.00	
394+65	PL	6	12	8.00	
395+85	DL	6	12	8.00	
395+85	PL	6	12	8.00	
TOTALS				330	36

SECTION "C" (PEORIA RD.) PATCHING				
CLASS D - 12"				
NORTH BOUND				
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 12" (SQ YD)
6+00	PL	6	12	8.00
2+00	DL	6	12	8.00
2+00	PL	6	12	8.00
75+20	DL	6	12	8.00
75+20	PL	6	12	8.00
74+75	PL	6	12	8.00
71+00	DL	6	12	8.00
71+00	PL	6	12	8.00
70+10	DL	6	12	8.00
70+10	PL	6	12	8.00
66+00	DL	6	12	8.00
66+00	PL	6	12	8.00
64+00	PL	6	12	8.00
55+00	PL	6	12	8.00
52+00	DL	6	12	8.00
52+00	PL	6	12	8.00
51+80	DL	10	12	13.33
51+80	PL	10	12	13.33
TOTALS				155
PATCHING SURVEY - PEORIA RD.				
CLASS D - 12"				
SOUTH BOUND				
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 12" (SQ YD)
74+75	DL	6	12	8.00
70+10	DL	6	12	8.00
70+10	PL	6	12	8.00
66+00	DL	6	12	8.00
66+00	PL	6	12	8.00
63+00	DL	6	12	8.00
63+00	PL	6	12	8.00
	DL	6	12	8.00
	PL	6	12	8.00
51+80	DL	10	12	13.33
51+80	PL	10	12	13.33
TOTALS				98

FILE NAME =	USER NAME = laughlinc1	DESIGNED -	REVISED -
er:\pw\work\PWIDOT\LAUHLINRL\dms47718\0372C35\shtr-schedule.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PATCHING SCHEDULES			
SCALE:	SHEET NO. 3 OF 3 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
658	*	SANGAMON	206	12
CONTRACT NO. 72C35				
ILLINOIS FED. AID PROJECT				