

**EARTH EXCAVATION (WIDENING) SCHEDULE**

LOCATION		20200500 VOLUME (CU YD)	
FAP 751 (IL 96) - SN 075-0004	22+190.00 TO 22+273.75	LT	11.6
		RT	11.6
	22+321.93 TO 22+405.00	LT	11.5
		RT	11.5
<b>TOTAL</b>			<b>46</b>

**PAVING SCHEDULE**

LOCATION		35600712 HMA BASE COURSE WIDENING 9"	40600200 BITUMINOUS MATERIALS (PRIME COAT)	40600300 AGGREGATE (PRIME COAT)	40600625 LEVELING BINDER (MM), N50	40603310 HMA SURFACE COURSE, MIX C, N50	44000155 HMA SURFACE REMOVAL 1 1/2"
		(SQ YD)	(TON)	(TON)	(TON)	(TON)	(TON)
FAP 751 (IL 96) - SN 075-0024	294+17.00 TO 295+75.36	LT	0.13	0.66	16.2	27.8	331.3
		RT	0.13	0.69	16.9	29.0	345.8
	296+64.45 TO 298+15.00	LT	0.12	0.62	15.2	26.0	309.3
		RT	0.12	0.64	15.8	27.0	321.6
FAP 751 (IL 96) - SN 075-0004	22+190.00 TO 22+273.75	LT	46.5	0.06	0.30	11.5	149.8
		RT	46.5	0.06	0.30	11.5	149.8
	22+321.93 TO 22+405.00	LT	46.1	0.06	0.30	11.4	148.6
		RT	46.1	0.06	0.30	11.4	148.6
<b>TOTAL</b>		<b>185</b>	<b>0.7</b>	<b>4</b>	<b>64</b>	<b>156</b>	<b>1905</b>

**TEMPORARY RAMP SCHEDULE**

LOCATION		40600990 AREA (SQ YD)
FAP 751 (IL 96) - SN 075-0024	294+17.00	17.8
	295+75.36	48.2
	296+64.45	48.2
	298+15.00	13.4
FAP 751 (IL 96) - SN 075-0004	221+90.00	17.8
	222+74.25	14.9
	223+21.43	14.9
	224+05.00	17.8
<b>TOTAL</b>		<b>193</b>

**SHORT-TERM PAVEMENT MARKING SCHEDULE**

LOCATION		70300100 LENGTH (FOOT)		
		NUMBER		
FAP 751 (IL 96) - SN 075-0024	294+17.00 TO 298+15.00	CENTERLINE	3	120
		EDGE LINE	3	96
FAP 751 (IL 96) - SN 075-0004	221+90.00 TO 224+05.00	CENTERLINE	2	48
		EDGE LINE	2	48
<b>TOTAL</b>			<b>312</b>	

**PAVEMENT MARKING SCHEDULE**

LOCATION		70300230 TEMPORARY 5" (FOOT)	78001120 PAINT 5" (FOOT)	78100100 RAISED REFL MKR (EACH)
FAP 751 (IL 96) - SN 075-0024	293+42 TO 299+03	CENTERLINE	YELLOW SKIP DASH	150
	294+17 TO 298+15	RT EDGE LINE	WHITE SOLID	398
	294+17 TO 298+15	LT EDGE LINE	WHITE SOLID	398
FAP 751 (IL 96) - SN 075-0004	220+37 TO 225+58	CENTERLINE	YELLOW SKIP DASH	140
	221+90 TO 224+05	LT EDGE LINE	WHITE SOLID	215
	221+90 TO 224+05	RT EDGE LINE	WHITE SOLID	215
<b>TOTAL</b>		<b>1516</b>	<b>1516</b>	<b>15</b>

FILE NAME =  
c:\pwork\pwidot\co\te\d0183187\067204

USER NAME = coxte  
-sht-schedule.dgn  
PLOT SCALE = 2.0000' / 1"  
PLOT DATE = Feb-18-2010 01:52:13PM

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**  
SCALE: NONE SHEET NO. 1 OF 6 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
751	D6 BRIDGE REPAIR 2009	PIKE	22	6
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72D44	