

JOINT REPAIR SCHEDULE		
JOINT	POLYMER CONCRETE (CU FT)	SILICONE JT. SEALER (FOOT)
E ABUT.	0	0
PIER 1	1.8	24.6
PIER 2	1.8	24.6
PIER 3	0	0
PIER 4	0	24.6
PIER 5	1.8	24.6
PIER 6	0	0
PIER 7	0	24.6
PIER 8	0	0
9A	0	0
9B	1.8	24.6
9C	0	0
9D	0	0
PIER 9	1.8	24.6
10A	1.8	24.6
10B	1.8	24.6
10C	1.8	24.6
10D	0	0
PIER 10	0	0
PIER 11	0	24.6
PIER 12	0	24.6
PIER 13	0	24.6
PIER 14	0	24.6
PIER 15	0	24.6
PIER 16	0	24.6
PIER 17	0	24.6
PIER 18	0	24.6
PIER 19	0	24.6
PIER 20	0	24.6
PIER 21	1.8	24.6
PIER 22	1.8	24.6
PIER 23	1.8	24.6
PIER 24	1.8	24.6
PIER 25	1.8	24.6
PIER 26	1.8	24.6
PIER 27	1.8	24.6
PIER 28	1.8	24.6
PIER 29	1.8	24.6
PIER 30	1.8	24.6
PIER 31	1.8	24.6
PIER 32	1.8	24.6
PIER 33	1.8	24.6
PIER 34	1.8	24.6
PIER 35	1.8	24.6
PIER 36	0	0
W ABUT.	0	0
TOTALS	41.4	861

DECK SURFACE PATCHING SCHEDULE			
SPAN	HMA SURF. REM. (DECK) (SQ YD)	INCIDENTAL HMA SURF. (TON)	BIT. MATL. (PRIME CT.) (TON)
9	66.7	3.7	0.03
10	146.7	8.3	0.06
TOTALS	213.4	12.0	0.09

SCHEDULES OF QUANTITIES
FAP 63 (US 24)
SECTION (1ZB)I-4
ADAMS COUNTY