

PAVEMENT MARKING SCHEDULE			
STATION	TYPE	PAINT PVT MK LINE 5"	
		WHITE	YELLOW
LT & RT 66+50 TO 88+32	EDGE LINE	4,364 FT	
RT 66+50 TO 68+16	NO PASS		166 FT
LT 66+50 TO 75+74	NO PASS		924 FT
RT 78+90 TO 88+32	NO PASS		942 FT
68+16 TO 88+32	SKIP DASH		510 FT
LT & RT 134+63 TO 191+57	EDGE LINE	11,388 FT	
LT 134+63 TO 144+78	NO PASS		1,015 FT
RT 164+60 TO 191+57	NO PASS		2,697 FT
LT 174+70 TO 191+57	NO PASS		1,687 FT
134+63 TO 174+70	SKIP DASH		1,000 FT
LT & RT 191+57 TO 197+50	NO PASS		1,194 FT
TOTALS		15,752 FT	10,135 FT

CONCRETE GUTTER, TYPE A				
STATION	CLASS SI CONCRETE OUTLET			CLASS SI GUTTER, TYPE A
	INLET	ENTRANCE	OUTLET	
RT 80+50 TO 80+86			6.8 CU YD	
RT 80+86 TO 82+85				199 FT
RT 82+85 TO 83+15		5.0 CU YD		
RT 83+15 TO 86+03				288 FT
RT 86+03 TO 86+15	0.9 CU YD			
TOTALS		12.7 CU YD		487 FT

HOT-MIX ASPHALT SHOULDERS, 8"	
STATION	
RT 80+00 TO 86+15	137 SQ YD
TOTALS	170.0 TON

SAW CUTS	
STATION	
RT 80+00 TO 86+15	615 LIN FT
TOTALS	615 LIN FT

AGGREGATE SHOULDERS, TYPE B	
STATION	
LT & RT 66+50 TO 74+50	30.3 TON
LT 79+00 TO 82+50	6.6 TON
RT 70+00 TO 80+00	1.9 TON
LT & RT 143+85 TO 171+75	105.8 TON
LT 176+50 TO 183+44	13.2 TON
RT 177+32 TO 183+44	11.6 TON
TOTALS	170.0 TON

MIXTURE REQUIREMENTS			
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT			
MIXTURE USE(S):	H.M.A S.C., MIX C, N50	PAVEMENT PATCHING	H.M.A SHOULDERS, 8"
AC/PG	PG 64-22	PG 64-22	PG 58-22
DESIGN AIR VOIDS:	4.0% @ N DESIGN = 50	4.0% @ N DESIGN = 50	2.0% @ N DESIGN = 30
MIXTURE COMP:	IL 9.5 OR 12.5	IL 19.0	IL 19.0
FRICTION AGG:	MIX "C"	N/A	N/A

NOTES:
STATIONS ARE APPROXIMATE.

SCHEDULES
SBI 96 (WARSAW SPUR)
SECTION 123 RS-6
HANCOCK COUNTY