

**SUMMARY OF QUANTITIES**

CODED NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																
				(25-3)B			(25-3)R				(25-3)BY			(25-3)BR						
				100% STATE ROADWAY J000-2A	100% STATE BRIDGE SN 025-0107 EB & SN 025-0108 X031-2A	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE ROADWAY J000-2A	100% STATE ROADWAY 1000	100% STATE SIGNING Y002-1C	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE BOX CULVERTS TUNNEL SN 025-2018 EB X228-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2017 WB X228-2A	100% STATE BRIDGE 025-0001 X271-2A	100% STATE BRIDGE 025-0018 X271-2A						
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	866	12			854													
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	869	36			833													
20100500	TREE REMOVAL, ACRES	ACRE	16.75	0.5			16.25													
20200100	EARTH EXCAVATION	CU YD	119780	6315			113465													
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	705				370					60	29					240		
20400800	FURNISHED EXCAVATION	CU YD	91325	6265			85060													
20700220	POROUS GRANULAR EMBANKMENT	CU YD	324									60	29						235	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1044		460							350	234							
20800150	TRENCH BACKFILL	CU YD	972				972													
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	210992	21837			189155													
* 25000200	SEEDING, CLASS 2	ACRE	47.75	6.25			41.5													
* 25000300	SEEDING, CLASS 3	ACRE	1.25				1.25													
* 25000350	SEEDING, CLASS 7	ACRE	62.5	6.25			56.25													
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4411	563			3848													
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4411	563			3848													
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4411	563			3848													
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.5				2.5													
* 25000750	MOWING	ACRE	49	6.25			42.75													
* 25100120	MULCH, METHOD 2	TON	98	12.5			85.5													
* 25100630	EROSION CONTROL BLANKET	SQ YD	4536				4536													
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	30	20			10													
28000305	TEMPORARY DITCH CHECKS	FOOT	7380	322			7058													
28000400	PERIMETER EROSION BARRIER	FOOT	28188	2704			25484													
28000500	INLET AND PIPE PROTECTION	EACH	65	3			62													
28001000	AGGREGATE (EROSION CONTROL)	TON	22	19			3													
28100105	STONE RIPRAP, CLASS A3	SQ YD	976				976													
28100107	STONE RIPRAP, CLASS A4	SQ YD	12802	91	2130		10581													
28200200	FILTER FABRIC	SQ YD	12802	91	2130		10581													
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	132106	10010			122096													
30201500	LIME	TON	1141.1	252.3			888.8													
30201800	SLAG-MODIFIED PORTLAND CEMENT	TON	1724.5				1724.5													
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	2757				2757													
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	136991	10010			126981													
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	5116				5116													
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	400				400													
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2060				2060													
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	5371				5371													
40300500	COVER COAT AGGREGATE	TON	102				102													
40300600	SEAL COAT AGGREGATE	TON	51				51													
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1288	14					1234										40	
40600300	AGGREGATE (PRIME COAT)	TON	26.3	0.3					25										1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	588	176															412	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	111																111	
40600990	TEMPORARY RAMP	SQ YD	269						220										49	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	1257	12					1204										41	

\* Specialty Items