

SUMMARY OF QUANTITIES

CODED NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																
				(25-3)B			(25-3)R			(25-3)BY			(25-3)BR							
				100% STATE ROADWAY J000-2A	100% STATE BRIDGE SN 025-0107 EB & SN 025-0108 X031-2A	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE ROADWAY J000-2A	100% STATE ROADWAY 1000	100% STATE SIGNING Y002-1C	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE SN025-0099 SN025-0100	100% STATE BOX CULVERTS TUNNEL SN 025-2018 EB X228-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2017 WB X228-2A	100% STATE BRIDGE 025-0001 X271-2A	100% STATE BRIDGE 025-0018 X271-2A					
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	77				77													
40800030	AGGREGATE (PRIME COAT)	TON	2				2													
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	349				349													
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	4594				4594													
42000540	PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	31393	1426			28992												975	
42001200	PAVEMENT FABRIC	SQ YD	31415	1426			28992	22											975	
42001300	PROTECTIVE COAT	SQ YD	12352	1426			10926													
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	284				284													
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	11				11													
42100360	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 13"	SQ YD	124143	9342			114801													
42100960	PAVEMENT REINFORCEMENT 13"	SQ YD	124143	9342			114801													
42101080	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE (SPECIAL)	EACH	4	4																
42101300	PROTECTIVE COAT	SQ YD	126011	11210			114801													
44000100	PAVEMENT REMOVAL	SQ YD	75297	6522			68775													
44000192	HOT-MIX ASPHALT REMOVAL (SPECIAL)	SQ YD	4682				4682													
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	16468					16468												
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2397				2397													
44000700	APPROACH SLAB REMOVAL	SQ YD	479	427			52													
44004000	PAVED DITCH REMOVAL	FOOT	1532				1532													
44004250	PAVED SHOULDER REMOVAL	SQ YD	38208	4413			32845												950	
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	29495	1019			28476													
44201043	CLASS B PATCHES, TYPE II, 16 INCH	SQ YD	492					492												
44201047	CLASS B PATCHES, TYPE III, 16 INCH	SQ YD	22					22												
44213200	SAW CUTS	FOOT	2866					2866												
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	7528	555			6973													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	81					81												
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	214	214																
48203100	HOT-MIX ASPHALT SHOULDERS	TON	734					723											11	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		2															
50102400	CONCRETE REMOVAL	CU YD	211.4				37.7				6.5	50.9	23.8			44			48.5	
50104400	CONCRETE HEADWALL REMOVAL	EACH	7				7													
50104650	SLOPE WALL REMOVAL	SQ YD	1826	1408															59	359
50105220	PIPE CULVERT REMOVAL	FOOT	296	15			281													
50157300	PROTECTIVE SHIELD	SQ YD	436								20					244			172	
50200100	STRUCTURE EXCAVATION	CU YD	1477		1441											24			12	
50200300	COFFERDAM EXCAVATION	CU YD	4172		4172															
50202901	COFFERDAM (LOCATION - 1)	EACH	1		1															
50202902	COFFERDAM (LOCATION - 2)	EACH	1		1															
50202903	COFFERDAM (LOCATION - 3)	EACH	1		1															
50202904	COFFERDAM (LOCATION - 4)	EACH	1		1															
50300100	FLOOR DRAINS	EACH	109		108															
50300225	CONCRETE STRUCTURES	CU YD	1809		1715.6											49.8			43.6	
50300254	RUBBED FINISH	SQ FT	737													323			414	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2076.9		1944.7						7.2					42.9			82.1	
50300260	BRIDGE DECK GROOVING	SQ YD	5605		4861		12									652			80	

FILE NAME =	USER NAME = paul	DESIGNED - ESW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMBINED SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
S:\projects\103\103-77\103-77.dgn		DRAWN - ESW	REVISED -			57/70	(25-3)R, BY, BR, B	EFFINGHAM	1416	3	
PLOT SCALE = 100.0000' / IN.		CHECKED - BRM	REVISED -			CONTRACT NO. 74296					
PLOT DATE = 3/23/2018		DATE - 09-18-09	REVISED -			SCALE:	SHEET NO. 2 OF 7 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		