

SUMMARY OF QUANTITIES

CODED NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE													
				(25-3)B			(25-3)R			(25-3)Y			(25-3)BR				
				100% STATE ROADWAY J000-2A	100% STATE BRIDGE SN 025-0107 EB & SN 025-0108 X031-2A	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE ROADWAY J000-2A	100% STATE ROADWAY I000	100% STATE SIGNING Y002-1C	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE SN025-0099 SN025-0100 SETLI-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2018 EB X228-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2017 WB X228-2A	100% STATE BRIDGE 025-0001 X271-2A	100% STATE BRIDGE 025-0018 X271-2A		
50300265	SEAL COAT CONCRETE	CU YD	698		698												
50300280	CONCRETE ENCASEMENT	CU YD	70.8		70.8												
50300300	PROTECTIVE COAT	SQ YD	7135.4		6091							26.4				819	199
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	6387		6387												
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	17305													7466	9839
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	26													18	8
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1													1	
50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1														1
50800105	REINFORCEMENT BARS	POUND	141,080					141,080									
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	780,410		671,250			1370				2050	43260	29800	12170	20510	
50800515	BAR SPLICERS	EACH	4015		3898											86	31
51100100	SLOPE WALL 4 INCH	SQ YD	400													48	352
51201800	FURNISHING STEEL PILES HP 14X73	FOOT	17566	148	17344			74									
51202305	DRIVING PILES	FOOT	17566	148	17344			74									
51203800	TEST PILE STEEL HP14X73	EACH	12		12												
51500100	NAME PLATES	EACH	4		2								1	1			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	334		184											91	59
52000320	NEOPRENE EXPANSION JOINT 2"	FOOT	232													111	121
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	26													18	8
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	28		28												
52100505	ANCHOR BOLTS, 5/8"	EACH	56		56												
52100520	ANCHOR BOLTS, 1"	EACH	36													36	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	166		32											72	62
52100540	ANCHOR BOLTS, 1 1/2"	EACH	16														16
54002020	EXPANSION BOLTS 3/4 INCH	EACH	248					118					96	34			
54003000	CONCRETE BOX CULVERTS	CU YD	891.5					463.7					255.3	172.5			
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	121					121									
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	204	14				190									
542A0253	PIPE CULVERTS, CLASS A, TYPE 1 48"	FOOT	9					9									
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	297	118				179									
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	27					27									
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	88					88									
542A1099	PIPE CULVERTS, CLASS A, TYPE 2 54"	FOOT	83					83									
542A1129	PIPE CULVERTS, CLASS A, TYPE 2 84"	FOOT	16					16									
542A1921	PIPE CULVERTS, CLASS A, TYPE 3 36"	FOOT	40					40									
542A2809	PIPE CULVERTS, CLASS A, TYPE 4 84"	FOOT	67					67									
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	36					36									
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	94					94									
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	39					39									
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4					4									
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	2				2									
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2					2									
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	4					4									
54213729	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 84"	EACH	1					1									
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	2					2									

Rev. 5-26-10

FILE NAME =
 USER NAME = paul
 DESIGNED - ESW
 DRAWN - ESW
 CHECKED - BRM
 DATE - 09-18-09

REVISIONS
 REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

COMBINED SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 7 SHEETS STA. TO STA.

F.A.I. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
 57/70 (25-3)R, BY, BR, B EFFINGHAM 1416 4
 CONTRACT NO. 74296

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT