SUMMARY OF QUANTITIES

CODED NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE (25-3)B 100% STATE ROADWAY J000-2A	(25-3)B 100% STATE BRIDGE SN 025-0107 EB & SN 025-0108 X031-2A	(25-3)B 100% STATE IMPACT ATTENUATORS SFTY-3N	(25-3)B	(25-3)R 100% STATE ROADWAY J000-2A	(25-3)R 100% STATE ROADWAY I000	(25-3)R ~~100% STATE SIGNING Y002-1C~~	(25-3)R ~~100% STATE IMPACT ATTENUATORS SFTY-3N~~	(25-3)R	(25-3)BY 100% STATE BOX CULVERTS TUNNEL SN 025-2018 EB X228-2A	(25-3)BY 100% STATE BOX CULVERTS TUNNEL SN 025-2017 WB X228-2A	(25-3)BR 100% STATE BRIDGE 025-0001 X271-2A	(25-3)BR 100% STATE BRIDGE 025-0018 X271-2A	
73400100	CONCRETE FOUNDATIONS	CU YD	70.2	13.4				56.8									
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	34.9					34.9									
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	4	1				3									
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	7					7									
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	8	2				6									
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	7					7									
78006100	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	119.2					119.2									
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1091	66				953	72								
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	29	24					5								
78200410	GUARDRAIL MARKERS, TYPE A	EACH	112	25				87									
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	15	4				11									
80400100	ELECTRIC SERVICE INSTALLATION	EACH	2					2									
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	154					154									
81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	592					592									
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	640					640									
81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	50					50									
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	18					18									
81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	3187					3187									
81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	12046					12046									
81603040	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	21,770					21,770									
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	1145					1145									
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1120					1120									
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	2210					2210									
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	30120					30120									
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	116					116									
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	16					16									
82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	2					2									
82109105	SIGN LIGHTING (HIGH PRESSURE SODIUM)	EACH	17					17									
82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1					1									
82500380	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 200AMP	EACH	1					1									
83004600	LIGHT POLE, ALUMINIUM, 50 FT. M.H., 15 FT. DAVIT ARM	EACH	116					116									
83057310	LIGHT POLE, WOOD, 55 FOOT, CLASS 4	EACH	16					16									
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	113					113									
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	308					308									
84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	16					16									
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	9					9									
84200804	REMOVAL OF POLE FOUNDATION	EACH	3					3									
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	3					3									
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2					2									
X0321778	SEISMIC RESTRAINER	EACH	28												12	16	
X0322729	MATERIAL TRANSFER DEVICE	TON	1257	12					1204						41		
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	4					4									
X0323236	TEMPORARY INLET	EACH	3					3									
* X0323388	TRAFFIC COUNTER	EACH	2					2									
* X0323644	PAVEMENT MARKING GROOVING	FOOT	85343	12657				61632	11054								
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1638		1638												
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	4630		4630												

*Specialty Items

Rev.

FILE NAME = S:\Projects\HED-00072.57-70\dgn\S Tr-L\summary_combined.dgn	USER NAME = paul	DESIGNED - ESW	REVISED -
		DRAWN - ESW	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED - BRM	REVISED -
	PLOT DATE = 3/23/2010	DATE - 09-18-09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

COMBINED SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 6 OF 7 SHEETS | STA. | TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	(25-3)R, BY, BR, B	EFFINGHAM	1416	7
		CONTRACT NO. 74296		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT