

SUMMARY OF QUANTITIES

CODED NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				(25-3)B			(25-3)R			(25-3)Y			(25-3)BR					
				100% STATE ROADWAY J000-2A	100% STATE BRIDGE SN 025-0107 EB & SN 025-0108 X031-2A	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE ROADWAY J000-2A	100% STATE ROADWAY I000	100% STATE SIGNING Y002-1C	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE SN 025-0099 SN 025-0100 SFTY-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2018 EB X228-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2017 WB X228-2A	100% STATE BRIDGE 025-0001 X271-2A	100% STATE BRIDGE 025-0018 X271-2A			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	862														388	474
X0325605	PAVEMENT MARKING GROOVING	SQ FT	401					401										
X0358300	REMOVE AND RELAY END SECTIONS	EACH	1					1										
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1													
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1													
X5020503	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 3	EACH	1		1													
X5020504	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 4	EACH	1		1													
X5041800	CONCRETE ANCHORS	EACH	30					30										
X5060601	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO.1	L SUM	1															
X5080600	MECHANICAL SPLICERS	EACH	1752		1548													
X5060602	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO.2	L SUM	1									204						
X6370250	CONCRETE BARRIER, VARIABLE CROSS SECTION 42" HEIGHT	FOOT	521					521										
XT013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1					1										
* X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	66911	11250				46147	9514									
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	11031	1407				8795	829									
* X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	6213					5589	624									
* X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	1190					1103	87									
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	591														591	
Z0012200	CONCRETE BRIDGE DECK SCARIFICATION (1/2 INCH)	SQ YD	652														652	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2				0.76									0.02	0.02
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	25														14	11
Z0017100	DOWEL BARS	EACH	1204						1204									
Z0018800	DRAINAGE SYSTEM	L SUM	1															1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	9		1				7								1	
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1						1									
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	13		1				11								1	
Z0054505	ROCK FILL - REPLACEMENT	TON	791					791										
Z0065730	SLOPE WALL SLURRY PUMPING	CU YD	341															341
Z0076850	UNSOUND CONCRETE REMOVAL	SQ YD	15.8														10.8	5
* A2C05065	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 5-GALLON	EACH	200					200										
* A2C07063	TREE, TAXODIUM DISTICHUM (BALD CYPRESS), CONTAINER GROWN, 3-GALLON	EACH	200					200										
* B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	350					350										
* B2001464	TREE, CORNUS MAS (CORNELIAN CHERRY DOG WOOD), 5' HEIGHT, SHRUB FOPM, BALLED AND BURLAPPED	EACH	200					200										
* B2006316	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	200					200										
* C2002048	SHRUB, CORYLUS AMERICANA (AMERICAN FILBERT), 4' HEIGHT, BALLED AND BURLAPPED	EACH	875					875										
* C2005965	SHRUB, RHUS GLABRA (SMOOTH SUMAC), 5-GALLON	EACH	875					875										
* C2C00363	SHRUB, AMOUPHA FRUITCOSA (INDIGO BUSH), CONTAINER GROWN, 3-GALLON	EACH	875					875										
* C2C00663	SHRUB, ARONIA MELANOCARPA VIKING (VIKING BLACK CHOKEBERRY), CONTAINER GROWN, 3-GALLON	EACH	875					875										
* C2C05724	SHRUB, RHUS AROMATICA (FRAGRANT SUMAC), 2' WIDTH, CONTAINER	EACH	875					875										
* C2C11624	SHRUB, VIBURNUM CARLESI (KOREANSPICE VIBURNUM), 2' HEIGHT, CONTAINER	EACH	875					875										
* C2C11736	SHRUB, VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 3' HEIGHT, CONTAINER	EACH	860					860										
* D2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	210					210										
* X7800100	PREFORMED THERMOPLASTIC PAVEMENT MARKING SHIELD	EACH	4					4										
X6023800	REMOVE AND RELOCATE INLETS	EACH	1	1														

* Specialty Items

Rev. 5-26-10