

PIPE UNDERDRAINS SCHEDULE

LOCATION		CONCRETE HEADWALL FOR PIPE DRAINS (EACH)	PIPE UNDERDRAINS 4" (FOOT)	PIPE UNDERDRAINS 4" (SPECIAL) (FOOT)	PIPE UNDERDRAINS 6" (FOOT)	PIPE UNDERDRAINS 6" (SPECIAL) (FOOT)	REMARKS
STATION TO STATION	SIDE						
SOUTH ROADWAY A							
STA 2015+01.00 TO STA 2016+74.50	LT/RT	2			347.0	20.0	PLUG AT STA 2015+01.00
STA 2016+75.50 TO STA 2019+99.00	LT/RT				647.0		PLUG AT STA 2019+99.00
STA 2020+00.00 TO STA 2023+24.00	LT	1			324.0	10.0	PLUG AT STA 2023+24.00
STA 2020+00.00 TO STA 2024+99.00	RT	1			499.0	10.0	PLUG AT STA 2024+99.00
STA 2023+25.00 TO STA 2024+99.00	LT	1			174.0	10.0	PLUG AT STA 2024+99.00
STA 2025+00.00 TO STA 2029+99.00	LT/RT	2			998.0	20.0	PLUG AT STA 2029+99.00
STA 2030+00.00 TO STA 2034+99.00	LT/RT	2			998.0	20.0	PLUG AT STA 2034+99.00
STA 2035+00.00 TO STA 2039+99.00	LT	1			499.0	10.0	PLUG AT STA 2039+99.00
STA 2038+82.60 TO STA 2039+99.00	RT				116.4	6.0	PLUG AT STA 2039+99.00
STA 2040+00.00 TO STA 2042+99.00	LT	1			299.0	10.0	PLUG AT STA 2042+99.00
STA 2040+00.00 TO STA 2044+99.00	RT	1			499.0	10.0	PLUG AT STA 2044+99.00
STA 2043+00.00 TO STA 2045+24.90	LT	1			224.9	10.0	PLUG AT STA 2045+24.90
STA 2045+00.00 TO STA 2049+99.00	RT	1			499.0	10.0	PLUG AT STA 2049+99.00
STA 2050+00.00 TO STA 2051+39.60	RT	1			139.6	10.0	PLUG AT STA 2051+39.60
STA 2066+96.00 TO STA 2071+74.00	RT	1			478.0	10.0	PLUG AT STA 2071+74.00
STA 2071+75.10 TO STA 2076+49.00	LT/RT	2			947.8	20.0	PLUG AT STA 2076+49.00
STA 2076+50.00 TO STA 2081+49.00	LT/RT	2			998.0	20.0	PLUG AT STA 2081+49.00
STA 2081+50.00 TO STA 2084+40.00	LT/RT	2			580.0	20.0	PLUG AT STA 2084+40.00
STA 2084+41.00 TO STA 2089+40.00	LT	1			499.0	10.0	PLUG AT STA 2089+40.00
STA 2084+49.50 TO STA 2088+59.70	RT				410.2	18.0	PLUG AT STA 2088+59.70; OUTLET AT STRUCTURE
STA 2088+60.70 TO STA 2093+06.60	RT				406.2	5.0	PLUG AT STA 2093+06.60; OUTLET AT STRUCTURE
STA 2089+41.00 TO STA 2084+04.00	LT	1			423.3	10.0	PLUG AT STA 2094+04.00
SOUTH ROADWAY B							
STA 2015+01.00 TO STA 2016+74.50	LT/RT	2			347.0	20.0	PLUG AT STA 2015+01.00
STA 2016+75.50 TO STA 2019+99.00	LT/RT				647.0		PLUG AT STA 2019+99.00
STA 2020+00.00 TO STA 2024+99.00	LT/RT	2			998.0	20.0	PLUG AT STA 2024+99.00
STA 2025+00.00 TO STA 2026+34.00	LT/RT	2			268.0	20.0	PLUG AT STA 2026+34.00
STA 2026+36.00 TO STA 2029+99.00	LT	1			363.0	10.0	PLUG AT STA 2026+36.00
STA 2030+00.00 TO STA 2034+13.80	LT	1			413.8	10.0	PLUG AT STA 2030+00.00
STA 2032+52.10 TO STA 2034+13.80	RT	1			161.7	10.0	PLUG AT STA 2032+52.10
STA 2034+14.80 TO STA 2039+08.00	LT/RT				986.4		PLUG AT STA 2039+08.00
STA 2039+09.00 TO STA 2042+74.90	LT	1			365.9	10.0	PLUG AT STA 2042+74.90
STA 2039+09.00 TO STA 2042+85.40	RT	1			376.4	10.0	PLUG AT STA 2042+85.40
STA 2045+56.90 TO STA 2050+59.00	LT	1			502.1	10.0	PLUG AT STA 2050+59.00
STA 2054+74.90 TO STA 2050+59.00	RT	1			484.1	10.0	PLUG AT STA 2050+59.00
STA 2050+60.00 TO STA 2055+59.00	LT/RT	2			998.0	20.0	PLUG AT STA 2055+59.00
STA 2055+60.00 TO STA 2058+92.50	RT	1			334.3	10.0	PLUG AT STA 2058+92.50
STA 2055+60.00 TO STA 2060+59.00	LT	1			496.9	10.0	PLUG AT STA 2060+59.00
STA 2060+60.00 TO STA 2065+59.00	LT	1			496.9	10.0	PLUG AT STA 2065+59.00
STA 2065+60.00 TO STA 2070+59.00	LT	1			496.9	10.0	PLUG AT STA 2070+59.00
STA 2070+60.00 TO STA 2075+59.00	LT	1			499.0	10.0	PLUG AT STA 2075+59.00
STA 2071+17.30 TO STA 2075+59.00	RT	1			441.7	10.0	PLUG AT STA 2075+59.00
STA 2075+60.00 TO STA 2080+59.00	LT/RT	2			998.0	20.0	PLUG AT STA 2080+59.00
STA 2080+60.00 TO STA 2085+59.00	LT/RT	2			998.0	20.0	PLUG AT STA 2085+59.00
STA 2085+60.00 TO STA 2087+58.80	LT/RT	2			397.6	20.0	PLUG AT STA 2087+58.80
STA 2087+60.00 TO STA 2092+54.00	RT	1			494.0	10.0	PLUG AT STA 2092+54.00
STA 2087+68.00 TO STA 2091+81.00	LT				413.0	18.0	PLUG AT STA 2091+81.00; OUTLET AT STRUCTURE
STA 2091+82.00 TO STA 2093+06.60	LT				406.8	5.0	PLUG AT STA 2093+06.60; OUTLET AT STRUCTURE
SUBTOTAL		52	0	0	24390.9	572.0	

PIPE UNDERDRAINS SCHEDULE

LOCATION		CONCRETE HEADWALL FOR PIPE DRAINS (EACH)	PIPE UNDERDRAINS 4" (FOOT)	PIPE UNDERDRAINS 4" (SPECIAL) (FOOT)	PIPE UNDERDRAINS 6" (FOOT)	PIPE UNDERDRAINS 6" (SPECIAL) (FOOT)	REMARKS
STATION TO STATION	SIDE						
SOUTH ROADWAY B							
STA 2092+55.00 TO STA 2094+04.00	RT	1			431.2	10.0	PLUG AT STA 2094+04.00
SOUTH ROADWAY C							
STA 13+01.00 TO STA 18+00.00	LT	1			499.0	10.0	PLUG AT STA 13+01.00
STA 18+01.00 TO STA 23+00.00	LT	1			499.0	10.0	PLUG AT STA 18+01.00
STA 23+01.00 TO STA 28+00.00	LT	1			499.0	10.0	PLUG AT STA 23+01.00
STA 28+01.00 TO STA 33+00.00	LT	1			494.5	10.0	PLUG AT STA 28+01.00
STA 28+60.60 TO STA 33+00.00	RT	1			444.9	10.0	PLUG AT STA 28+60.60
SOUTH ROADWAY D							
STA 5025+85.90 TO STA 5028+14.00	LT/RT	2			456.2	20.0	PLUG AT STA 5025+85.90
STA 5028+15.00 TO STA 5033+09.00	LT/RT	2			988.0	20.0	PLUG AT STA 5028+15.00
STA 5033+10.00 TO STA 5038+07.70	LT/RT	2			995.4	20.0	PLUG AT STA 5033+10.00
STA 5038+08.70 TO STA 5040+66.40	LT				258.7		PLUG AT STA 5040+66.40
STA 5038+08.70 TO STA 5043+02.70	RT				492.4		PLUG AT STA 5043+02.70
STA 5043+03.70 TO STA 5047+99.00	RT	1			496.9	10.0	PLUG AT STA 5047+99.00
STA 5048+00.00 TO STA 5052+96.00	RT	1			498.7	10.0	PLUG AT STA 5052+96.00
SOUTH RAMP F							
STA 10+00.00 TO STA 13+50.00	LT/RT	2	700.0	20			PLUG AT STA 10+00.00
STA 13+51.00 TO STA 14+68.40	RT		120.9	6			PLUG AT STA 13+51.00; OUTLET AT STRUCTURE
STA 13+51.00 TO STA 18+50.70	LT	1	498.7	10			PLUG AT STA 13+51.00
SOUTH RAMP G							
STA 10+40.80 TO STA 14+04.00	RT	1	363.2	10			PLUG AT STA 10+40.80
STA 14+05.00 TO STA 17+99.50	RT	1	394.5	10			PLUG AT STA 14+05.00
STA 16+56.40 TO STA 18+69.80	LT	1	215.3	10			PLUG AT STA 16+56.40
STA 18+00.50 TO STA 20+79.00	RT		275.8				PLUG AT STA 20+79.00
STA 18+70.70 TO STA 23+61.50	LT		505.7				PLUG AT STA 23+61.50
STA 20+80.00 TO STA 23+61.50	RT	1	278.5	10			PLUG AT STA 23+61.50
I-57/70 WESTBOUND							
STA 2093+07.60 TO STA 2096+99.00	RT				391.4	5.0	PLUG AT STA 2096+99.00; OUTLET AT STRUCTURE
STA 2094+05.00 TO STA 2098+79.00	LT	1			474.0	10.0	PLUG AT STA 2098+79.00
STA 2097+00.00 TO STA 2101+36.10	RT				436.1	5.0	PLUG AT STA 2101+36.10; OUTLET AT STRUCTURE
STA 2098+80.00 TO STA 2103+44.00	LT	1			464.0	10.0	PLUG AT STA 2103+44.00
STA 2101+37.10 TO STA 2103+44.00	RT				206.9	5.0	PLUG AT STA 2103+44.00; OUTLET AT STRUCTURE
I-57/70 WESTBOUND							
STA 2093+07.60 TO STA 2096+99.00	LT				391.4	5.0	PLUG AT STA 2096+99.00; OUTLET AT STRUCTURE
STA 2094+05.00 TO STA 2098+79.00	RT	1			474.0	10.0	PLUG AT STA 2098+79.00
STA 2097+00.00 TO STA 2101+36.10	LT				436.1	5.0	PLUG AT STA 2101+36.10; OUTLET AT STRUCTURE
STA 2098+80.00 TO STA 2103+44.00	RT	1			464.0	10.0	PLUG AT STA 2103+44.00
STA 2101+37.10 TO STA 2103+44.00	LT				206.9	5.0	PLUG AT STA 2103+44.00; OUTLET AT STRUCTURE
STRUCTURES		LT/RT	6				
SUBTOTAL			31	3352.6	76	10998.7	210.0
TOTAL			83	3352.6	76	35389.6	782.0
PAY TOTAL			83	3353	76	35390	782

MISCELLANEOUS DRAINAGE SCHEDULE

LOCATION		PIPE CULVERTS, CLASS D, TYPE 1 15" (FOOT)	PIPE CULVERTS, CLASS D, TYPE 1 24" (FOOT)	PIPE CULVERTS, CLASS D, TYPE 1 36" (FOOT)	METAL END SECTIONS 15" (EACH)	METAL END SECTIONS 18" (EACH)	METAL END SECTIONS 24" (EACH)	METAL END SECTIONS 36" (EACH)	PIPE DRAINS 15" (FOOT)	PIPE DRAINS 18" (FOOT)	PIPE DRAINS 24" (FOOT)	PIPE DRAINS 36" (FOOT)	CONCRETE HEADWALLS (CU YD)	CONCRETE COLLAR (EACH)	CONCRETE THRUST BLOCKS (EACH)	CONCRETE ANCHORS (EACH)
STATION TO STATION	SIDE															
ROADWAY A																
2047+50.00 TO 2047+88.96	LT						1				43					3
2047+88.96 TO 2048+27.16	LT										36					2
2059+85.00	LT								9					1		
ROADWAY B																
2046+04.68	RT					1				94			1.7		2	6
2070+27.00	LT						1				68					5
2070+58.97	LT							1			27					
RAMP F																
10+26.38	LT				1				89						1	6
FRONTAGE ROAD 1354																
2+86.06	LT/RT		59				2									
5+32.24	LT/RT		35				2									
FRONTAGE ROAD 2																
15+40.55	LT/RT			39						2						
28+25.30	RT	36			2											
TOTAL		36	94	39	3	1	6	3	98	94	147	27	1.7	1*	3*	22*

*NOT A TOTAL QUANTITY

FILE NAME = S:\Projects\102-0000\102-0000.dwg

USER NAME = paul

DESIGNED - ESW

REVISED -

DRAWN - ESW

REVISED -

CHECKED - BRM

REVISED -

DATE - 02-25-08

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES, SOUTH TRI LEVEL

SCALE: SHEET NO. 3 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	(25-3)R	EFFINGHAM	1416	156
CONTRACT NO. 74296				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				