

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
310	60-16-1A1B,42-1A1B	MADISON AND JERSEY	481	3
STA		TO STA		
EXISTING CONDITIONS:				

CONTRACT NO. 76318

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
				JERSEY COUNTY				MADISON COUNTY
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE (ARCH)	80% FEDERAL 20% STATE BRIDGE (BEAM)	80% FEDERAL 20% STATE RETAINING WALL	80% FEDERAL 20% STATE ROADWAY
CODE NUMBER	ITEM	UNITS	TOTAL	I000-2A	X024-2A	X081-2A	Y007	I000-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	252	252				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	4,065	4,065				
20100500	TREE REMOVAL, ACRES	ACRE	20.40	16.00				4.40
20200100	EARTH EXCAVATION	CU YD	318,833	318,389				444
20300100	CHANNEL EXCAVATION	CU YD	3,593	3,593				
20400800	FURNISHED EXCAVATION	CU YD	207,793	205,293				2,500
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	430	430				
20800150	TRENCH BACKFILL	CU YD	2500	2400				100
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	61,790	61,790				
25000200	SEEDING, CLASS 2	ACRE	38.25	37.25				1.00
25000300	SEEDING, CLASS 3	ACRE	8.00	8.00				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4,166	4,076				90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4,166	4,076				90
25000600	POTASSIUM FERTILIZER NUTRIENT	PCUND	4,166	4,076				90
25000700	AGRICULTURAL GROUND LIMESTONE	TON	16.0	15.5				0.5
25100115	MULCH, METHOD 2	ACRE	36.00	35.00				1.00
25100630	EROSION CONTROL BLANKET	SQ YD	70,155	70,155				

Rev.

REVISED 03/09/2010 (BLA)