

SUMMARY OF QUANTITIES

F&P ROUTE	SECTION	C	TOTAL SHEETS
310	60-16-1&18,42-1&18	MADISON, ILLINOIS	48
STA	TO STA	EXISTING CONDITIONS:	
		CONTRACT NO.	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
				JERSEY COUNTY				MADISON COUNTY
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE (ARCH)	80% FEDERAL 20% STATE BRIDGE (BEAM)	80% FEDERAL 20% STATE RETAINING WALL	80% FEDERAL 20% STATE ROADWAY
CODE NUMBER	ITEM	UNITS	TOTAL	I000-2A	X024-2A	X081-2A	Y007	I000-2A
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	2,122	2,122				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1,000	1,000				
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19				
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	37	37				
40300500	COVER COAT AGGREGATE	TON	110	110				
40300600	SEAL COAT AGGREGATE	TON	110	110				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33	31				2
40600300	AGGREGATE (PRIME COAT)	TON	1.1	1.1				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	599	599				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	80	80				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	494	169				325
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	8,734	8,734				
40603315	HOT-MIX ASPHALT, SURFACE COURSE, MIX 'C', N70	TON	731	731				
40603345	HOT-MIX ASPHALT, SURFACE COURSE, MIX 'D', N90	TON	1,939	,939				
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	44,420	60,986				3,434
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	107	107				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	600		600			

Rev.