

### EARTHWORK

LOCATION	1	2	3	4
	EARTH EXCAVATION (CU YD)	*EARTH EXCAVATION (ADJUSTED FOR 25% SHRINKAGE) (CU YD)	*EMBANKMENT (FILL) (CU YD)	EARTHWORK BALANCE WASTE (+) OR FURNISHED EXCAVATION (-) (COL 2 - COL 3) (CU YD)
<b>STAGE 1A</b>				
US 67	184,999	138,749	341,493	-202,744
CONNECTOR	1,951	1,463	0	1,463
STAGECOACH	10,179	7,634	33	7,601
335 PRIVATE ENTRANCE	3,313	2,485	490	1,995
INGHAM RUNAROUND	745	559	1,699	-1,140
TRINTY RUNAROUND	17	13	823	-810
<b>SUBTOTAL STAGE 1A</b>	<b>201,204</b>	<b>150,903</b>	<b>344,538</b>	<b>-193,635</b>
<b>STAGE 1B</b>				
QUARRY ROAD	11,607	8,705	7,020	1,685
INGHAM	5,101	3,826	2,922	904
JUN	960	720	440	280
<b>SUBTOTAL STAGE 1B</b>	<b>17,668</b>	<b>13,251</b>	<b>10,382</b>	<b>2,869</b>
<b>STAGE 2</b>				
US 67	78,863	59,147	88,596	-29,449
CONNECTOR	815	611	88	523
DOMINO SERVICE LANE	3,435	2,576	1,324	1,252
DOMINO LANE	93	70	1	69
INGHAM	6,532	4,899	605	4,294
INGHAM ACCESS DRIVE	782	587	1,311	-724
STAGECOACH	9,441	7,081	1	7,080
<b>SUBTOTAL STAGE 2</b>	<b>99,961</b>	<b>74,971</b>	<b>91,926</b>	<b>-16,955</b>
DITCH CHECKS	0	0	72	-72
<b>TOTAL</b>	<b>318,833</b>	<b>239,125</b>	<b>446,846</b>	<b>-207,793</b>
*TOTAL EXCESS EXCAVATION				2,869

EXCESS EXCAVATION IN STAGE 1B SHALL BE USED TO REDUCE FURNISHED EXCAVATION IN STAGE 2  
ITEMS MARKED WITH AN ASTERISK(\*) ARE FOR INFORMATION ONLY.

### SEEDING

LOCATION	SEEDING CLASS 2 (ACRE)	SEEDING CLASS 3 (ACRE)	MULCH METHOD 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (LB)	PHOSPHORUS FERTILIZER NUTRIENT (LB)	POTASSIUM FERTILIZER NUTRIENT (LB)	AGRICULTURAL GROUND LIMESTONE (TON) (CLASS 3)
<b>US 67</b>							
STAGE 1	18.25	3.00	18.25	1,913	1,913	1,913	6.0
STAGE 2	12.50	3.00	12.50	1,395	1,395	1,395	6.0
<b>QUARRY ROAD</b>							
STAGE 1	1.75	0.50	1.75	203	203	203	1.0
<b>CONNECTOR</b>							
STAGE 1	0.25	0.00	0.25	23	23	23	
<b>DOMINO LANE SERVICE ROAD</b>							
STAGE 2	1.25	0.00	1.25	113	113	113	
<b>DOMINO LANE</b>							
STAGE 2	0.25	0.00	0.25	23	23	23	
<b>NORTH INGHAM</b>							
STAGE 1	0.75	0.25	0.75	90	90	90	0.5
STAGE 2	0.50	0.25	0.50	68	68	68	0.5
<b>INGHAM ACCESS DR</b>							
STAGE 2	0.50	0.25	0.50	68	68	68	0.5
<b>STAGE COACH ROAD</b>							
STAGE 1	0.75	0.25	0.75	90	90	90	0.5
STAGE 2	0.75	0.25	0.75	90	90	90	0.5
<b>JUN ACCESS ROAD</b>							
STAGE 2	0.50	0.0	0.50	45	45	45	
<b>335 PRIVATE ROAD</b>							
STAGE 1	0.25	0.3	0.25	45	45	45	0.5
<b>EROSION CONTROL BLANKET DEDUCT</b>							
TOTAL	38.25	8.00	36.00	4,166	4,166	4,166	16.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULE OF QUANTITIES

FAP ROUTE 310  
 SECTION 60-16-1&1B,42-1&1B  
 MADISON AND JERSEY COUNTIES

DRAWN BY: RLK

CHECKED BY: CAS