

CONTROLLER #17

CRKT#	FROM/TO	UD 2*4 *4G XLPUSE 1 81603025	UD 2*6 *6G XLPUSE 1 81603035	UD 2*2*2G XLPUSE 1 1/4 81603065	EC C XLP USE 3-1C 6 81702415	REM ELCBL FR CON 89502300	COMMENT
17A	X6 B1		151				
17A	B1 B2		369				
17A	B2 B3		223				
17A	B3 B4		202				
17A	B4 B5		168				
17A	B5 B6		420				
17A	B6 B7		420				
17A	B7 X8		176				
17A	C5 C4		309				
17A	C4 C3		270				
17A	C3 C2		565				
17A	C2 C1		303				
17A	B4 C3		185		58		2" DIA. PUSHED
17A	X19 X21		233		77		2" DIA. PUSHED
17A	X21 X14		340		65		3" DIA. PUSHED
17A	X14 X12		319				
17A	X12 X10		158		80	80	1 1/4" ATS
17A	C1 X10		174				
17A	X14 X23		389			193	3" DIA. PUSHED
17A	X10 CNTLR#17		157				
17B	D1 D2		317				
17B	D2 D3		256				
17B	D3 D4		268				
17B	D4 D5		481				
17B	D5 D6		261				
17B	A2 A3		184				
17B	A3 A4		157				
17B	A4 A5		201				
17B	A5 A6		243				
17B	A6 X4		316				
17B	X4 X2		235				
17B	X2 A1		146				
17B	D4 A4		133		68		2" DIA. PUSHED
17B	X1 X3		228				
17B	X3 X5		250		75		2" DIA. PUSHED
17B	X5 X7		232				
17B	X7 X9		235				
17B	X9 X11		238				
17B	X11 U.P. LGT.		142				
17B	U.P. LGT. X13		200				
17B	X13 X15		202				
17B	X15 X17		208				
17B	X4 X11		113		90		2" DIA. PUSHED
17B	X17 CNTLR#17		35				
17C	M120 A&B M121 A&B		410				
17C	M121 A&B M122 A&B		330				
17C	M122 A&B M123 A&B		330				
17C	M123 A&B M124 A&B		325				
17C	M124 A&B M125 A&B		330				
17C	M125 A&B M126 A&B		330				
17C	M126 A&B M127 A&B		330				
17C	M127 A&B M128 A&B		330				
17C	M135 A&B M134 A&B		330				
17C	M134 A&B M133 A&B		330				
17C	M133 A&B M132 A&B		330				
17C	M132 A&B M131 A&B		330				
17C	M131 A&B M130 A&B		330				
17C	M130 A&B M129 A&B		330				
17C	M129 A&B M134 A&B		330				
17C	M128 A&B CNTLR#17		666		63		3" DIA. PUSHED

CONTROLLER #17

CRKT#	POLE #	ROADWAY	STATION	50 FT. M.H. W/TB 15 FT. MAST ARM HORIZONTAL MOUNT			50 FT. M.H. 15 FT. MAST ARM HORIZONTAL MOUNT			50 FT. M.H. W/ T.B 2-8 FT. MAST ARM HORIZONTAL MOUNT	
				400W	310W	250W	400W	310W	250W	400W	310W
				16" DIA.	16" DIA.	16" DIA.	16" DIA.	16" DIA.	16" DIA.	18" DIA.	
17B	A1	RAMP A	1+70								
17B	A2	RAMP A	3+57			1					
17B	A3	RAMP A	5+45	1							
17B	A4	RAMP A	7+38			1					
17B	A5	RAMP A	9+75			1					
17B	A6	RAMP A	12+42			1					
17A	B1	RAMP B	6+22			1					
17A	B2	RAMP B	8+95			1					
17A	B3	RAMP B	11+35			1					
17A	B4	RAMP B	13+70			1					
17A	B5	RAMP B	15+63	1							
17A	B6	RAMP B	18+17		1						
17A	B7	RAMP B	21+37		1						
17A	C1	RAMP C	2+30		1						
17A	C2	RAMP C	5+33				1				
17A	C3	RAMP C	10+77					1			
17A	C4	RAMP C	13+50					1			
17B	C5	RAMP C	16+62					1			
17B	D1	RAMP D	4+68						1		
17B	D2	RAMP D	7+85						1		
17B	D3	RAMP D	10+50						1		
17B	D4	RAMP D	13+28						1		
17B	D5	RAMP D	17+85			1					
17B	D6	RAMP D	20+45						1		
17B	X1	STATE ST. RT.	86+60	1							
17B	X2	STATE ST. LT.	96+15						1		
17B	X3	STATE ST. RT.	88+85				1				
17B	X4	STATE ST. LT.	98+40						1		
17B	X5	STATE ST. RT.	91+23						1		
17A	X6	STATE ST. LT.	101+63				1				
17B	X7	STATE ST. RT.	93+55					1			
17A	X8	STATE ST. LT.	103+65						1		
17B	X9	STATE ST. RT.	95+90						1		
17A	X10	STATE ST. LT.	106+60						1		
17B	X11	STATE ST. RT.	98+32						1		
17A	X12	STATE ST. LT.	109+20					1			
17B	X13	STATE ST. RT.	101+63						1		
17A	X14	STATE ST. LT.	112+40						1		
17B	X15	STATE ST. RT.	103+65						1		
17B	X17	STATE ST. RT.	105+73						1		
17A	X19	STATE ST. RT.	107+70						1		
17A	X21	STATE ST. RT.	109+93						1		
17A	X23	STATE ST. RT.	115+25				1				
17C	M120 A&B	BARRIER	890+90								2
17C	M121 A&B	BARRIER	894+20								2
17C	M122 A&B	BARRIER	897+50								2
17C	M123 A&B	BARRIER	900+80								2
17C	M124 A&B	BARRIER	904+05								2
17C	M125 A&B	BARRIER	907+35								2
17C	M126 A&B	BARRIER	910+65								2
17C	M127 A&B	BARRIER	913+95								2
17C	M128 A&B	BARRIER	917+25							2	
17C	M129 A&B	BARRIER	920+55							2	
17C	M130 A&B	BARRIER	923+85								2
17C	M131 A&B	BARRIER	927+15								2
17C	M132 A&B	BARRIER	930+45								2
17C	M133 A&B	BARRIER	933+75								2
17C	M134 A&B	BARRIER	937+05							2	
17C	M135 A&B	BARRIER	940+35								2

FILE NAME =	USER NAME = prestonme	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>ELECTRIC CABLE, UNIT DUCT, POLE</b> <b>AND LUMINAIRE SCHEDULES 8 OF 18</b>	F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr\pwwork\XPWIDOT\PRESTONME\dms65337\d	76c07+sh+light.dgn	DRAWN -	REVISED -			255	DISI_8_LIGHT_POLE_2009-1		146	28	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 76009					
	PLOT DATE = 6/29/2010	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					