

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000 80% FED 20% STATE	-----	-----	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000 80% FED 20% STATE	-----	-----
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SO YD	136	136			70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	817	817		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	91.5	91.5			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	7500	7500		
40600300	AGGREGATE (PRIME COAT)	TON	438.7	438.7			X72400310	REMOVE SIGN PANEL - TYPE 1	SO FT	29	29		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	7240.9	7240.9			X73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	29	29		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			X78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1946	1946		
40600990	TEMPORARY RAMP	SO YD	3082	3082			X78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	42542	42542		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	11129.1	11129.1			X78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2451	2451		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.8	1.8			X78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	817	817		
40800030	AGGREGATE (PRIME COAT)	TON	8.6	8.6			X78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1107	1107		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	321	321			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1032	1032		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	14208.8	14208.8			X80300100	LOCATING UNDERGROUND CABLE	FOOT	75	75		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5866	5866			X88600600	DETECTOR LOOP REPLACEMENT	FOOT	440	440		
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	8843	8843			X4421000	PARTIAL DEPTH PATCHING	TON	184	184		
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	4329	4329			X4422030	PARTIAL DEPTH REMOVAL 3"	SO YD	876	876		
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SO YD	1585	1585			Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM	1	1		
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SO YD	70	70			Z0075310	TIE BARS 3/4"	EACH	2281	2281		
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SO YD	3783	3783			XZ0076600	TRAINEES	HOOR	1000	1000		
44213100	PAVEMENT FABRIC	SO YD	1900	1900									
60260100	INLETS TO BE ADJUSTED	EACH	32	32									
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	32	32									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10									
67100100	MOBILIZATION	L SUM	1	1									
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1									
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1									
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1									
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1									
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	35	35									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7500	7500									
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1946	1946									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	42542	42542									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2451	2451									

0Y080
*Specialty Items

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.W RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - ---	REVISED - ---			9257	(28-1-122-1)BS-1	SI-CLAIR	43	3	
	PLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _ (ILLINOIS) FED. AID PROJECT			
	PLOT DATE = #DATE#	DATE - ---	REVISED - ---			CONTRACT NO. 16Q58					