

SIDEROAD SCHEDULE						
SIDEROAD	L/R	WIDTH	INCIDENTAL HMA SUFACING	(40800020) BIT. MAT. PRIME COAT	(40800030) AGG. PRIME COAT	TEMPORARY RAMPS
		(FOOT)	(SQ YD)	(TON)	(TON)	(SQ YD)
STA. 251+35		48				26.7
TURN LANE		16				8.9
INTERSECTION OF IL 13		24				13.3
BRITTANY LN.	L	103	6.4	0.04	0.17	57.2
TERRACE AVE.	R	90	5.6	0.03	0.15	50.0
MIDWAY CIRCLE	R	90	5.6	0.03	0.15	50.0
FRANK SCOTT PRKWAY	L	230	14.3	0.08	0.38	127.8
FRANK SCOTT PRKWAY	R	230	14.3	0.08	0.38	127.8
47TH ST.	L	90	5.6	0.03	0.15	50.0
RUTH ST.	L	90	5.6	0.03	0.15	50.0
FREEDOM DR.	R	90	5.6	0.03	0.15	50.0
WASHINGTON ST.	R	110	6.8	0.04	0.18	61.1
FREINDLY DR.	R	100	6.2	0.03	0.17	55.6
MAIN ST.	R	256	15.9	0.09	0.43	142.2
MAIN ST.	L	256	15.9	0.09	0.43	142.2
BALLAVUE AVE.	L	90	5.6	0.03	0.15	50.0
46TH ST.	L	90	5.6	0.03	0.15	50.0
45TH ST.	R	68	4.2	0.02	0.11	37.8
45TH ST.	L	90	5.6	0.03	0.15	50.0
44TH ST.	R	90	5.6	0.03	0.15	50.0
44TH ST.	L	90	5.6	0.03	0.15	50.0
43RD ST.	L	90	5.6	0.03	0.15	50.0
42ND ST.	R	90	5.6	0.03	0.15	50.0
42ND ST.	L	90	5.6	0.03	0.15	50.0
41ST ST.	R	90	5.6	0.03	0.15	50.0
40TH ST.	L	100	6.2	0.03	0.17	55.6
40TH ST.	R	90	5.6	0.03	0.15	50.0
39TH ST.	L	102	6.3	0.04	0.17	56.7
39TH ST.	R	102	6.3	0.04	0.17	56.7
38TH ST.	L	90	5.6	0.03	0.15	50.0
ROYAL HEIGHTS	L	220	13.7	0.08	0.37	122.2
37TH ST.	R	220	13.7	0.08	0.37	122.2
DEVONSHIRE DR.	L	90	5.6	0.03	0.15	50.0
EDWARDS DR.	L	90	5.6	0.03	0.15	50.0
CHRISTOPHER DR.	L	90	5.6	0.03	0.15	50.0
COLUMBUS DR.	R	90	5.6	0.03	0.15	50.0
BUCKINGHAM	L	90	5.6	0.03	0.15	50.0
CANTERBURY	R	90	5.6	0.03	0.15	50.0
FOSTER	R	90	5.6	0.03	0.15	50.0
IVANHOE	L	90	5.6	0.03	0.15	50.0
CHAUCER	L	90	5.6	0.03	0.15	50.0
17TH ST.	R	220	13.7	0.08	0.37	122.2
17TH ST.	L	220	13.7	0.08	0.37	122.2
16TH ST.	R	90	5.6	0.03	0.15	50.0
OLD CASEYVILLE	L	90	5.6	0.03	0.15	50.0
15TH ST.	R	90	5.6	0.03	0.15	50.0
CASEYVILLE	R	105	6.5	0.04	0.18	58.3
STA. 258+75		82				45.6
STA. 259+73		176				97.8
STA. 261+46		40				22.2
TOTAL:			321	1.8	8.6	3082

C&G/MEDIAN SCHEDULE								
STA.	TO	STA.	C&G REMOVAL	CON. MEDIAN SURFACE REMOVAL	MEDIAN REMOVAL (PARTIAL DEPTH)	CLASS "C" PATCHING TYPE IV, 10"	TIE BARS	PAVEMENT FABRIC
			FOOT	SQ FT	SQ FT	SQ YD	EACH	SQ YD
139+36	TO	143+59	846	1721.96		282	338	282
144+33	TO	148+89	912	1333.31		304	365	304
149+55	TO	151+90	470	689.47		156.7	188	156.7
174+56	TO	177+16	520	727.03		173.3	208	173.3
178+20	TO	179+77	314	453.02		104.7	126	104.7
197+95	TO	200+70	550	815.67		183.3	220	183.3
201+17	TO	202+19	204	293.03		68	82	68
215+35	TO	217+03	336	466.96		112	134	112
217+62	TO	219+24	324	452.07		108	130	108
229+00	TO	230+07	214	294.12		71.3	86	71.3
230+59	TO	231+67	216	298.41		72	86	72
241+48	TO	243+59	422	592.04		140.7	169	140.7
244+18	TO	246+04	372	518.23		124	149	124
252+62	TO	256+00			3705			
259+74	TO	260+57	166	186.73				
260+53	TO	261+36			624			
TOTAL:			5866	8843	4329	1900	2281	1900

SIGN PANEL SCHEDULE		
STATION	REMOVE SIGN PANEL TYPE I	REMOVE GROUND MOUNTED SIGN SUPPORT
	EACH	EACH
139+45	1	1
143+48	1	1
144+45	1	1
145+79	1	1
148+73	1	1
149+68	1	1
151+79	1	1
174+65	1	1
177+09	1	1
178+28	1	1
179+74	1	1
198+00	1	1
200+60	1	1
201+24	1	1
202+13	1	1
215+38	1	1
216+94	1	1
217+72	1	1
219+20	1	1
229+04	1	1
230+05	1	1
260+68	1	1
231+62	1	1
241+53	1	1
243+50	1	1
244+28	1	1
246+00	1	1
259+85	1	1
260+00	1	1
TOTAL:	29	29

FILE NAME *	USER NAME = #USER#	DESIGNED - ---	REVISED - ---
#FILE#		DRAWN - ---	REVISED - ---
	PLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---
	PLOT DATE = #DATE#	DATE - ---	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9267	(28-1-122-1)RS-1	ST. CLAIR	43	6
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				CONTRACT NO. 76058