



SICKLER RD.
LT. STA. 3+14
(SEE SIDE ROAD
SCHEDULE, SHT. 9)

PT EQ STA 424+32.12 (BK) =
STA. 0+32.12 (AP) PC STA 3+13.90

CURVE DATA
 $\Delta = 63^\circ 19' 02''$
 $D = 10^\circ 29' 56''$
 $T = 2357.13'$
 $R = 3822.69'$
 $L = 4224.44'$
 $E = 668.31'$

CL FAP 312 (IL 3)

PROP. PROJECT LOCATION 1 BEGINS
STA. 396+14.34 (BUTT JOINT)
SEE MEDIAN DETAIL, SHT'S 24 & 26.

PR. AGGREGATE WEDGE
SHOULDERS - 2' WIDE
BEGINS LT. & RT.
STA. 401+00

EASTMAN RD.
RT. STA. 412+10
(SEE SIDE ROAD
SCHEDULE, SHT. 9)

EX. PCC PAVEMENT
EX. BIT. SURFACED PAVEMENT
STA. 397+64

UNIFORM 24' PAVEMENT
BEGINS STA. 401+00

EASTMAN RD.
RT. STA. 398+35
(SEE SIDE ROAD
SCHEDULE, SHT. 9)

PR. AGGREGATE SHOULDERS
TYPE B - 1 1/2"
LT. & RT. STA. 396+15 TO
LT. & RT. STA. 401+00 (SEE
DETAIL, SHT. 24)

EQ STA 45+18.48 (BK) =
PC STA 382+07.68 (AH)

EQ. STA. 387+23.00 (IL 3) =
STA. 386+90.03 (IL 149)

FILE NAME =
ct:\pw\work\PIW100T\MCCORDKR\d0181703\sh

USER NAME = mcoordkr
details.dgn
PLOT SCALE = 400.0000' / IN.
PLOT DATE = 5/3/2010

DESIGNED - ---
DRAWN - ---
CHECKED - ---
DATE - ---

REVISED - ---
REVISED - ---
REVISED - ---
REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN LAYOUT - LOCATION 1
STA. 396 ± 14.34 TO STA. 401 ± 50
SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	12385-5+130.13185-4	JACKSON	35	13
CONTRACT NO. 78195				

ILLINOIS FED. AID PROJECT