

SUMMARY OF QUANTITIES

ITEM DESCRIPTION			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	860
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	13
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	140.4
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	45218
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	5434
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	695
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	430
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	56
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	291
* 78100105	RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)	EACH	2
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	32
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	17
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	238
* X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1
X4020700	AGGREGATE SURFACE COURSE, TYPE B 8 INCH	SQ YD	730
Z0010555	DITCH CLEANING	FOOT	4502



• SPECIALTY ITEMS

USER NAME = Heyen00951 <small>\\08jobs\08L0221\CADD\Road\Sheet\09003401\FV\c-50L_sq.dgn</small> PLOT SCALE = 1.0000 "/>	DESIGNED - m.heyen DRAWN - r.Johnson CHECKED - m.heyen DATE - 3/26/2010	REVISED - REVISED - REVISED - REVISED -
---	--	--

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
SHEET 3 OF 3**

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
500	09-00334-01-PV	VERMILION	69	5
JOB NO. C-95-330-10		CONTRACT NO. 91440		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			