

EARTHWORK SCHEDULE						
LOCATION	20200100					
	A	B	C	D		
	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT, ADJUSTED FOR SHRINKAGE (20%)	EMBANKMENT	EARTHWORK BALANCE EXCESS (+) OR SHORTAGE (-)		
BEGIN STATION	END STATION	OFFSET	CU YD	CU YD	CU YD	CU YD
BEGINNING OF PROJECT - LIBERTY LANE INTERSECTION						
72+55.00	115+03.89		4279	3423	1035	2388
SUBTOTAL			4279	3423	1035	2388
LIBERTY LANE INTERSECTION - STRUCTURE 092-0186						
116+51.77	13+62.00		570	456	1183	-728
SUBTOTAL			570	456	1183	-728
STRUCTURE 092-0186 - POLAND ROAD INTERSECTION						
15+59.00	168+83.84		434	347	210	137
SUBTOTAL			434	347	210	137
TOTAL			5280	4225	2430	1800

EQUATIONS USED
 B = A * 0.80
 D = B - C

LOCATION	SEEDING SCHEDULE								
	25000210	25000400	25000500	25000600	25000700	25100115	28000250		
	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING		
BEGIN STATION	END STATION	OFFSET	ACRES	POUNDS	POUNDS	POUNDS	TONS	ACRES	POUND
BEGINNING OF PROJECT - LIBERTY LANE INTERSECTION									
72+55.00	115+03.89		2.25	203	203	203	4.5	2.25	450
SUBTOTAL			2.25	203	203	203	4.5	2.25	450
LIBERTY LANE INTERSECTION - STRUCTURE 092-0186									
116+51.77	13+62.00		1.25	113	113	113	2.5	1.25	250
SUBTOTAL			1.25	113	113	113	2.5	1.25	250
STRUCTURE 092-0186 - POLAND ROAD INTERSECTION									
15+59.00	168+83.84		0.50	45	45	45	1.0	0.50	100
SUBTOTAL			0.50	45	45	45	1.0	0.50	100
TOTAL			4.00	360	360	360	8.0	4.00	800



I:\09_jobs\06L0221\CADD\Road\Sheet\09003401PV\c-602_schedu1.es.dgn	USER NAME = Heyen00951	DESIGNED - m.heyen	REVISED -
		DRAWN - r.johnson	REVISED -
	PLOT SCALE = 50.0000' / in.	CHECKED - m.heyen	REVISED -
	PLOT DATE = 04/30/2010	DATE - 3/26/2010	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 SHEET 4 OF 4

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
500	09-00334-01-PV	VERMILION	69	15
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 91440	