

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X028-2A		
20700110	POROUS GRANULAR EMBANKMENT	TON	585	585		
28100107	STONE RIPRAP, CLASS A4	SQ YD	130	130		
28200200	FILTER FABRIC	SQ YD	130	130		
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	37	37		
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	144	144		
42001200	PAVEMENT FABRIC	SQ YD	144	144		
44000100	PAVEMENT REMOVAL	SQ YD	144	144		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	66	66		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	82	82		
51500100	NAME PLATES	EACH	1	1		
X5400900	BOX CULVERT END SECTIONS, SPECIAL	EACH	2	2		
54021207	PRECAST CONCRETE BOX CULVERT (M273)	FOOT	78	78		
*63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	487.5	487.5		
*63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	50	50		
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	525	525		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	350	350		
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	9	9		
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
X0324952	DETOUR SIGNING	L SUM	1	1		
*Z0054505	ROCK FILL - REPLACEMENT	TON	148	148		

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -
c:\pwwork\PWIDOT\TEASLEYCK\dms60131\0784992\shd-soq.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 "/ IN.	CHECKED -	REVISED -
	PLOT DATE = 1/13/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

**Specialty Items* Rev.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1720	58-1	Richland	14	3
			CONTRACT NO. 94992	
ILLINOIS FED. AID PROJECT				