



EXCAVATION DETAIL

PCC PAVEMENT 10"

STA 150+93 TO 151+47 144 SQ YD

PAVEMENT REMOVAL

STA 150+93 TO 151+47 144 SQ YD

GUARDRAIL REMOVAL

RT STA 149+40 TO 152+15 275 FOOT
 LT STA 150+44 TO 152+94 250 FOOT
 TOTAL 525 FOOT

PAINT PAVEMENT MARKING - LINE 4"

STA 150+66 TO 151+74 EDGE LINES 216
 STA 150+66 TO 151+74 NPZ 108
 STA 150+66 TO 151+74 DASHES 26
 TOTAL 350

GUARDRAIL SCHEDULE

	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURE	GUARDRAIL MARKER, TYPE A	TERMINAL MARKER, DIRECT APPLIED
	FOOT	EACH	FOOT	EACH	EACH
RT STA 148+20 TO 148+70		1			1
RT STA 148+70 TO 151+07	237.5		25	4	
RT STA 151+07 TO 151+32				1	
RT STA 151+32 TO 151+82	50	1			1
RT STA 151+82 TO 152+32					
LT STA 150+20 TO 150+70		1			1
LT STA 150+70 TO 151+07	37.5		25	1	
LT STA 151+07 TO 151+32					
LT STA 151+32 TO 152+95	162.5	1		3	
LT STA 152+95 TO 153+45					1
TOTALS	487.5	4	50	9	4

FILE NAME =	USER NAME = teasleyok	DESIGNED -	REVISED -
g:\pw_work\PWIDOT\TEASLEYCK\dms60131\0794992-sht-details.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 1/13/2010		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES & DETAILS			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1720	58-1	Richland	14	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 94992	