



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 19, 2021

SUBJECT FAU Route 0379 (IL 126)  
Project HSIP-STP-2JLK(820)  
Section 119CH&TS  
Will & Kendall Counties  
Contract No. 62G10  
Item No. 12, July 30, 2021 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added pages 142 & 143 to the Special Provisions
4. Revised sheets 5, 6, 8, 13 & 29 of the Plans
5. Added the 663 Forms to the Additional Information folder on the website

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

LIGHT EMITTING DIODE (LED) SIGNAL HEAD AND OPTICALLY PROGRAMMED LED SIGNAL HEAD .....	61
TRAFFIC SIGNAL BACKPLATE.....	65
DETECTOR LOOP .....	65
RADAR VEHICLE DETECTION SYSTEM .....	67
EMERGENCY VEHICLE PRIORITY SYSTEM.....	68
3D MODEL FEEDBACK .....	69
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE).....	70
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) .....	72
BLENDED FINELY DIVIDED MINERALS (BDE).....	73
COMPENSABLE DELAY COSTS (BDE).....	74
CONCRETE END SECTIONS FOR PIPE CULVERTS (BDE).....	77
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	79
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) .....	81
DISPOSAL FEES (BDE) .....	90
ELECTRIC SERVICE INSTALLATION (BDE) .....	92
EMULSIFIED ASPHALTS (BDE) .....	93
ENGINEER’S FIELD OFFICE AND LABORATORY (BDE) .....	97
FUEL COST ADJUSTMENT (BDE).....	100
GEOTECHNICAL FABRIC FOR PIPE UNDERDRAINS AND FRENCH DRAINS (BDE).....	102
MOBILIZATION (BDE) .....	105
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE).....	105
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE) .....	106
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) .....	116
SILT FENCE, INLET FILTERS, GROUND STABILIZATION AND RIPRAP FILTER FABRIC (BDE).....	128
STEEL PLATE BEAM GUARDRAIL MANUFACTURING (BDE) .....	133
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) .....	134
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) .....	134
TEMPORARY PAVEMENT MARKING (BDE).....	135
TRAFFIC CONTROL DEVICES - CONES (BDE).....	137
WARM MIX ASPHALT (BDE) .....	138
WEEKLY DBE TRUCKING REPORTS (BDE).....	139
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) .....	140
WORKING DAYS (BDE) .....	141
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC) .....	142

Revised 7/19/2021

## REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

**Description.** This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

**Contract Specific Sites.** The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

**Soil Disposal Analysis.** When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

### Site 3078V-1: Agricultural Land, 100-200 Blocks of IL 126, Unincorporated Na-Au-Say and Plainfield Townships, Kendall County and Will County

- Station 95+60 to Station 97+00 (CL IL 126), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic and Manganese.
- Station 98+80 to Station 100+40 (CL IL 126), 0 to 65 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic.
- Station 100+40 to Station 101+90 (CL IL 126), 0 to 70 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic and Manganese.
- Station 101+90 to Station 103+95 (CL IL 126), 0 to 55 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Lead.
- Station 103+95 to Station 106+00 (CL IL 126), 0 to 45 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Lead.
- Station 106+00 to Station 108+00 (CL IL 126), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Iron and Manganese.
- Station 95+20 to Station 95+60 (CL IL 126), 0 to 40 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Manganese.

Added 7/19/2021

- Station 95+60 to Station 97+00 (CL IL 126), 0 to 40 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic and Manganese.
- Station 97+00 to Station 99+00 (CL IL 126), 0 to 40 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Manganese.
- Station 21+50 to Station 22+35 (CL County Line Road), 0 to 30 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Manganese.

At the Site 3078V-1 Agricultural Land property, Manganese was detected at a concentration potentially exceeding the TACO Tier 1 Soil Remediation Objective for the Construction Worker exposure route in Boring 1-08, from the sample interval 0 to 3 feet deep, as noted in the Final Preliminary Site Investigation Report for this project, submitted May 21, 2021, by Huff & Huff. Procedures shall be implemented to protect site workers and observers from hazards encountered during construction activities in locations containing contaminated materials, pursuant to Article 669 of the Standard Specifications for Road and Bridge Construction manual.

Site 3078V-4: Springhole Creek, 100 Block of IL 126, Unincorporated Na-Au-Say and Plainfield Townships, Kendall County

- Station 99+00 to Station 100+20 (CL IL 126), 0 to 110 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Manganese.
- Station 23+50 to Station 24+00 (CL County Line Road), 0 to 70 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic.

Site 3078V-5: Vacant Land, 26000 Block of IL 126, Unincorporated Plainfield Township, Will County

- Station 22+35 to Station 24+95 (CL County Line Road), 0 to 40 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic.
- Station 100+60 to Station 101+90 (CL IL 126), 0 to 90 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic.
- Station 101+90 to Station 106+00 (CL IL 126), 0 to 45 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Manganese.

**Work Zones**

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:  
**None**

Added 7/19/2021