

SUMMARY OF QUANTITIES		100% STATE SFTY-IB	
CODE #	PAY ITEM	UNITS	TOTAL
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	313.9
35800100	PREPARATION OF BASE PAVEMENT,	SQ YD	267
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY 7 INCH	SQ YD	65.6
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	1193.8
42400500	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQ FT	878
42400800	DETECTABLE WARNINGS	SQ FT	46
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	73.0
44000600	SIDEWALK REMOVAL	SQ FT	258.3
44004700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	928.6
542A0213	PIPE CULVERTS, CLASS A, TYPE 1 8"	FOOT	2
60602800	CONCRETE GUTTER, TYPE B	FOOT	92.9
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	155.4
B2013466	T-MALUS GOLD RAIN (GOLD RAIN CRABAPPLE), 6" HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3
X0324938	LIMESTONE REPLACEMENT	SQ FT	37.3
XX000882	WOOD FENCE	FOOT	41.1
XX001758	WOOD FENCE REMOVAL	FOOT	73.7
XX002063	LIGHTING SYSTEM COMPLETE	L SUM	1
XX003121	TRENCH DRAIN, SPECIAL	FOOT	15.5
XX003181	GATES COMPLETE (SET OF 2)	EACH	1
XX003461	EARTHWORK EXCAVATION, SPECIAL	L SUM	1
X0301446	GATE, SPECIAL	EACH	1
B1012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	88
B1900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	70

PAVING SCHEDULE								
LOCATION	PC CONC PAVEMENT 7"	PC CONC SIDEWALK 5	AGG BASE CSE B 4	DETECTABLE WARNINGS	PC CONC SIDEWALK SPC	PC CONC GUTTER TYP B	PREP OF BASE	LIMESTONE REPLACEMENT
	(SQ YD)	(SQ FT)	(SQ YD)	(SQ FT)	(SQ FT)	(FOOT)	(SQ YD)	(SQ FT)
DAVID DAVIS HOUSE								
100+59.89, 33.83' LT TO 100+85.43, 58.64' LT	65.6		65.6					
100+85.37, 9.31' LT TO 100+90.37, 9.26' LT				10				
100+85.37, 9.31' LT TO 100+90.38, 15.26' LT		30.0	3.3					
100+85.38, 18.81' LT TO 100+97.46, 78.11' LT		496.0	55.1					
100+93.87, 9.26' LT TO 101+86.78, 10.24' LT			18.1			92.9		
100+93.89, 10.98' LT TO 102+26.28, 24.93' LT		667.8	74.2					
101+85.66, 8.62' RT TO 102+55.92, 28.49' LT							267	
102+22.08, 22.22' LT TO 102+27.37, 23.24' LT				10				
102+52.06 TO 102+54.06				13				
102+54.06 TO 103+89.14			97.6		878			
103+89.14 TO 103.91.14				13				
104+03.16, 6.24' RT TO 104+06.92, 5.98' LT								37.3
TOTAL =	65.6	1193.8	313.9	46	878	92.9	267	37.3

REMOVAL ITEMS				
LOCATION (STATION TO STATION)	SIDEWALK REMOVAL	SIDEWALK REMOVAL (SPECIAL)	DRIVEWAY REMOVAL	WOOD FENCE REMOVAL
	(SQ FT)	(SQ FT)	(SQ YD)	(FOOT)
DAVID DAVIS HOUSE				
100+59.89, 33.83' LT TO 100+93.14, 33.91' LT			73.0	
100+73.42, 17.81' LT TO 101+05.17, 17.98' LT				31.8
100+85.78, 42.78, LT TO 100+97.34, 78.16' LT	258.3			
100+89.85, 63.64' LT TO 100+98.07, 63.89' LT				8.2
100+98.07, 63.89' LT TO 100+98.14, 78.32' LT				14.4
102+02.78, 18.31' LT TO 102+07.79, 18.44' LT				10.3
102+07.79, 18.44' LT TO 102+08.10, 32.69' LT				5.0
102+54.07 TO 103+91.18		891.3		
104+03.16 TO 104+06.92		37.3		
TOTAL =	258.3	928.6	73.0	73.7

MOBILIZATION	
LOCATION	QUANTITY (LSUM)
ENTIRE PROJECT	1 LSUM
TOTAL =	1 LSUM

LIST OF STANDARDS

- 424001-05 CURB RAMPS FOR SIDEWALKS
- 606201-02 CONCRETE GUTTER, TYPE B
- 701501-05 URBAN LANE CLOSURE 2L 2W - UNDIVIDED
- 701901-01 TRAFFIC CONTROL DEVICES

GENERAL NOTES

- ALL ELEVATIONS ARE REFERENCED TO ELEVATIONS ESTABLISHED BY VASCONCELLES ENGINEERING CORP.
- WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER AND AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. IF THE ENGINEER DECIDES TO HAVE THE CONTRACTOR RESET THE MONUMENT, THIS WORK WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04.
- THE CONTRACTOR SHALL CONTACT J.U.L.I.E. PRIOR TO ANY EXCAVATION TO HAVE ALL PUBLIC AND PRIVATE UTILITIES LOCATED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.26 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS (800) 892-0123. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED. SEE SPECIAL PROVISIONS FOR STATUS OF UTILITIES, WITH UTILITY COMPANIES LISTED.
- ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
- ALL DETAILS IN THE PLANS SHALL GOVERN CONSTRUCTION OF THIS PROJECT, AND IN CASE OF CONFLICT WITH ANY STANDARD DRAWINGS INCLUDED, THE SAID DETAILS SHALL TAKE PRECEDENCE AND GOVERN.

MISCELLANEOUS ITEMS

LOCATION (STATION TO STATION)	GATES COMPLETE (SET OF 2)	PIPE CULVERTS 8"	LIGHTING UNIT COMPLETE	TRENCH DRAIN SPECIAL	WOOD FENCE	EARTH EXCAVATION SPECIAL	TRAFFIC CONT&PROT 701501	PAINT PVT MK LINE 6"	T-MALUS GOLD RAIN 6'	GATE SPECIAL
	(EACH)	(FOOT)	(EACH)	(FOOT)	(FOOT)	(L SUM)	(L SUM)	(FOOT)	(EACH)	(EACH)
DAVID DAVIS HOUSE										
ENTIRE PROJECT						1	1			
100+73.42, 17.81' LT TO 100+79.20, 17.76' LT					5.7					
100+79.20, 17.76' LT TO 100+84.95, 17.79' LT					5.8					
100+84.43, 16.31' LT TO 100+93.88, 10.24' LT				15.5						
100+84.94, 17.82' LT TO 100+90.94, 17.90' LT	1									
100+85.33, 11.56' LT			1							
100+90.95, 17.90' LT TO 100+97.23, 18.02' LT					6.3					
100+91.93, 16.16' LT TO 100+94.62, 17.53' LT		2								
100+91.95, 19.42' LT			1							
100+91.95, 31.15' LT			1							
100+91.95, 42.90' LT			1							
100+97.23, 18.02' LT TO 101+05.17, 17.98' LT					8.0					
100+98.55, 54.67' LT			1							
100+98.55, 66.41' LT			1							
101+02.98, 53.16' LT									1	
101+03.02, 64.50' LT									1	
101+03.07, 74.43' LT									1	
102+02.78, 18.31' LT TO 102+07.79, 18.44' LT					5.0					
102+07.79, 18.44' LT TO 102+07.97, 26.70' LT					10.3					
102+08.01, 28.69' LT TO 102+08.10, 32.69' LT										1
102+22.08, 22.22' LT TO 102+54.06, 3.25' LT								155.4		
TOTAL =	1	2	6	15.5	41.1	1	1	155.4	3	1

FILE NAME =	USER NAME = #USER#	DESIGNED - T.T.P.	REVISED -
#FILEL#		DRAWN - S.D.K.	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - R.H.D.	REVISED -
	PLOT DATE = #DATE#	DATE - 2/24/09	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY & SCHEDULE OF QUANTITIES, STANDARDS, & GENERAL NOTES

DAVID DAVIS STATE HISTORIC SITE

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		MCLEAN	7	2
SCALE:		SHEET NO. 2 OF 7 SHEETS		CONTRACT NO. 46027
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		