

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	INDEX OF SHEETS, INDEX OF STATE STANDARDS, GENERAL NOTES, AND SUMMARY OF QUANTITIES
3	LOCATION PLAN - FLUTED KNEE WALLS
4-7	PROPOSED PLANS SB I-94 (DAN RYAN) STA. 1216+50 TO STA. 1250+00 - CONTRACT 26B LOCATION
8-10	PROPOSED PLANS SB I-94 (DAN RYAN) STA. 1256+50 TO STA. 1273+00 - CONTRACT 26C LOCATION
11-13	PROPOSED PLANS SB I-94 (DAN RYAN) STA. 1273+00 TO STA. 1289+50 - CONTRACT 26D LOCATION
14	PROPOSED PLAN SB I-94 (DAN RYAN) STA. 1309+00 TO STA. 1314+50 - CONTRACT 22E LOCATION
15-18	PROPOSED PLANS SB I-94 (DAN RYAN) STA. 1326+50 TO STA. 1348+50 - CONTRACT 26E LOCATION
19	CHAIN LINK FENCE, 42" ATTACHED TO STRUCTURE (SPECIAL) DETAILS
20	MISCELLANEOUS FENCING DETAILS
21	CHAIN LINK GATE (SPECIAL) DETAILS
22-25	CHAIN LINK GATE ASSEMBLY (SPECIAL) PLAN, NOTES, ELEVATIONS, SECTIONS, AND DETAILS
26	TC-10 DIST 1, TRAFFIC CONTROL AND PROTECTION SPECIAL FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
27	TC-17 DIST 1, TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES
28	TC-18 DIST 1, SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
29	TC-22 DIST 1, ARTERIAL ROAD INFORMATION SIGN

INDEX OF STATE STANDARDS

STANDARD NO.	TITLE
000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
664001-02	CHAIN LINK FENCE
701456	PARTIAL EXIT RAMP CLOSURE FREEWAY/EXPRESSWAY
701601-00	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701701-00	URBAN LANE CLOSURE MULTILANE INTERSECTION
701801-04	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
720006-02	SIGN PANEL ERECTION DETAILS

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		100% STATE
			TOTAL	SFTY-4A	
66410700	CHAIN LINK GATES(SPECIAL)	EACH	3		3
67100100	MOBILIZATION	L SUM	1		1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
X0326311	RELOCATE EXISTING SIGN PANEL (SPECIAL)	EACH	9		9
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52		52
X6640050	CHAIN LINK FENCE, 42" ATTACHED TO STRUCTURE (SPECIAL)	FOOT	5383		5383
X6640500	CHAIN LINK GATE ASSEMBLY (SPECIAL)	EACH	2		2
Z0022800	FENCE REMOVAL	FOOT	5611		5611
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1

GENERAL NOTES:

- THE CONTRACTOR SHALL NOT SET UP A YARD OR FIELD OFFICE ON IDOT PROPERTY WITHOUT WRITTEN PERMISSION FROM IDOT.
- THE CONTRACTOR SHALL TAKE ALL NECESSARY SAFETY PRECAUTIONS TO PROTECT AND PROVIDE ACCESS TO ABUTTING PROPERTY, UTILITIES, PEDESTRIANS, AND VEHICULAR TRAFFIC.
- NIGHT OPERATIONS SHALL NOT BE ALLOWED.
- ALL ELEVATIONS SHOWN ARE BASED ON THE CHICAGO CITY DATUM OF 0.00, WHICH IS 579.19 FEET ABOVE MEAN TIDE NEW YORK. (NAVD 88)
- ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT NO GAP REMAINS BETWEEN PROPOSED FENCING OR WHERE PROPOSED FENCING TERMINATES AND EXISTING FENCE REMAINS IN PLACE. THE COST OF CLOSING THIS GAP SHALL BE INCLUDED WITH "CHAIN LINK FENCE, 42" ATTACHED TO STRUCTURE (SPECIAL)"
- THIS CONTRACT INCLUDES THE INSTALLATION OF FENCE ON KNEE WALLS THAT ARE CONSTRUCTED IN (5) DIFFERENT CONTRACTS. SEE LOCATION PLAN FOR CONTRACT NUMBERS.
- THE ENGINEER SHALL BE ALLOWED ACCESS TO THE FIELD OFFICE IN USE FOR KNEE WALL CONTRACT 62975 (25F).
- THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS FOR THE PROTECTION OF EXISTING PLANT MATERIAL FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS.
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH THE RESPECTIVE UTILITIES OF THE CITY OF CHICAGO. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL THE CHICAGO UTILITY ALERT NETWORK AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, CABLE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED). CONTACT THE CHICAGO DEPARTMENT OF WATER MANAGEMENT PERMIT SECTION AT (312) 747-7893 FOR WATER AND SEWER LOCATIONS.
- WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS. THE ENGINEER OR AN AUTHORIZED SURVEYOR AGENT WILL WITNESS OR OTHERWISE REFERENCE AND RESET MONUMENTS AS NECESSARY. ALL PROPERTY CORNERS EXCEPT THOSE WITHIN AREAS WHERE THE SCHEDULE, IF PROVIDED, SHOWS PLACEMENT OF R.O.W. MARKERS SHALL REMAIN UNDISTURBED.
- THE LOCATIONS OF VARIOUS ITEMS SUCH AS PAVEMENT, RETAINING WALLS, AND DRAINAGE STRUCTURES BUILT IN CONTRACTS UNDER CONSTRUCTION DURING THESE PLANS IS BASED ON THE PUBLISHED CONTRACT PLAN DRAWINGS AVAILABLE DURING DESIGN.
- A "BOXED" NOTE INDICATES AN ITEM OF WORK THAT IS NOT PAID FOR SEPARATELY, BUT IS PAID FOR AS PART OF ANOTHER ITEM LISTED IN THE SUMMARY OF QUANTITIES.
- ALL EXISTING FENCE TO BE REMOVED SHALL REMAIN IN PLACE UNTIL THE PROPOSED FENCE HAS BEEN INSTALLED.

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)INDEX OF SHEETS, INDEX OF STATE
STANDARDS, GENERAL NOTES,
AND SUMMARY OF QUANTITIESSCALE: NONE DRAWN BY: MAF
DATE: FEBRUARY 13, 2009 CHECKED BY: TGB, MI