

INCIDENTAL HOT-MIX ASPHALT SURFACING

LOCATION	QUANTITY (TON)
*JOBSITE	820
TOTAL	820

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

LOCATION	QUANTITY (FOOT)
STATION	OFFSET
16+05 TO 16+53	LT 18.8
23+53 TO 24+50	LT 96.9
15+04 TO 16+51	RT 147.0
23+60 TO 23+81	RT 6.3
27+85 TO 35+34	LT/RT 1498.0
TOTAL	1767.0

MEDIAN SURFACE REMOVAL AND REPLACEMENT

LOCATION	QUANTITY (SQ FT)
STATION	
US ROUTE 30	
27+85 TO 35+34	7490
TOTAL	7490

MODULAR GLARE SCREEN SYSTEM

LOCATION	QUANTITY (FOOT)
PRESTAGE - 17+40 TO 23+50	312
STAGE I - 4+40 TO 31+00	2076
STAGE II - 9+78 TO 36+70	372
IL 394 - 285+84 TO 302+32	984
TOTAL	3744

SHOULDER RUMBLE STRIP

LOCATION	QUANTITY (SQ YD)
NB IL 394 - 292+57 TO 302+32	975
SB IL 394 - 285+84 TO 298+45	1261
TOTAL	2236

TRAFFIC CONTROL AND PROTECTION, STANDARD 701421

LOCATION	QUANTITY (L SUM)
STATION	
JOBSITE	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701431

LOCATION	QUANTITY (EACH)
STATION	
JOBSITE	3
TOTAL	3

TRAFFIC CONTROL SURVEILLANCE

LOCATION	QUANTITY (CAL DAY)
*JOBSITE	26
TOTAL	26

CHANGEABLE MESSAGE SIGN

LOCATION	QUANTITY (CAL MO)
*JOBSITE	16
TOTAL	16

SHORT TERM PAVEMENT MARKING

LOCATION	QUANTITY (FOOT)
*JOBSITE	1000
TOTAL	1000

TEMPORARY PAVEMENT MARKING - LINE 6"

LOCATION	QUANTITY (FOOT)
PRESTAGE - 17+40 TO 23+50	624
STAGE I - 4+40 TO 31+00	4152
STAGE II - 9+78 TO 36+70	4896
IL 394 - 285+84 TO 302+32	1968
TOTAL	11640

TEMPORARY PAINT PAVEMENT MARKING, LINE 4"

LOCATION	QUANTITY (FOOT)
*JOBSITE	1000
TOTAL	1000

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (SQ FT)
STATION	
PRESTAGE - 17+40 TO 23+50	661
STAGE I - 4+40 TO 31+00	7635
STAGE II - 9+78 TO 36+70	9139
IL 394 - 285+84 TO 302+32	1672
TOTAL	19107

TEMPORARY CONCRETE BARRIER

LOCATION	QUANTITY (FOOT)
PRESTAGE - 17+40 TO 23+50	312
STAGE I - 4+40 TO 31+00	2076
STAGE II - 9+78 TO 36+70	372
IL 394 - 285+84 TO 302+32	984
TOTAL	3744

RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	QUANTITY (FOOT)
STAGE II	2076
TOTAL	2076

REPLACEMENT REFLECTOR

LOCATION	QUANTITY (EACH)
IL 394 - 285+84 TO 302+32	110
TOTAL	110

BARRIER WALL MARKERS, TYPE C

LOCATION	QUANTITY (EACH)
JOBSITE	1764
TOTAL	1764

PAVEMENT MARKING REMOVAL

LOCATION	LENGTH (FOOT)	QUANTITY (SQ FT)
STATION		
WHITE - (SKIP DASH, 4")		
04+39.22 TO 29+90.00 RT	2550.78	212.6
12+00.12 TO 36+70.00 LT	2470	823.3
WHITE - (SOLID, 4")		
09+70.00 TO 36+70.00 LT & RT	2700	1800.0
DOUBLE YELLOW - (SOLID 4")		
09+70.00 TO 36+70.00 MEDIAN	2700	1800.0
NW LOOP RAMP GORE		385.3
SE LOOP RAMP GORE		437.2
NE RAMP GORE		1389.1
IL 394 - 285+84 TO 302+32		4050.0
TOTAL		10897.5

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	QUANTITY (EACH)
STATION TO STATION	
PRE-STAGE (TWO-WAY AMBER)	
9+70 TO 17+50 (MED)	52
22+50 TO 29+90 (MED)	44
STAGE I (ONE-WAY CRYSTAL)	
9+70 TO 29+90 (RT)	101
12+00 TO 34+50 (LT)	124
STAGE II (ONE-WAY CRYSTAL)	
4+39.22 TO 9+70 (RT)	27
TOTAL	348

TEMPORARY INFORMATION SIGNING

LOCATION	QUANTITY (SQ FT)
*JOBSITE	116
TOTAL	116

TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE

LOCATION	QUANTITY (SQ FT)
*JOBSITE	108
TOTAL	108

SHOULDER RUMBLE STRIP REMOVAL

LOCATION	QUANTITY (SQ YD)
NB IL 394 - 292+57 TO 302+32	975
SB IL 394 - 285+84 TO 298+45	1261
TOTAL	2236

WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH

LOCATION	QUANTITY (FOOT)
STATION	
PRESTAGE - 17+40 TO 23+50	1149
STAGE I - 4+40 TO 31+00	7364
STAGE II - 9+78 TO 36+70	10006
TOTAL	18519

WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH

LOCATION	QUANTITY (FOOT)
STATION	
STAGE II - 9+78 TO 36+70	780
IL 394 - 285+84 TO 302+32	627
TOTAL	1407

WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH

LOCATION	QUANTITY (FOOT)
STATION	
NB IL 394 - 292+57 TO 302+32	2414
SB IL 394 - 285+84 TO 298+45	3119
TOTAL	5533

TRAFFIC CONTROL AND PROTECTION, (EXPRESSWAYS)

LOCATION	QUANTITY (L SUM)
STATION	
JOBSITE	1
TOTAL	1

TRAFFIC CONTROL SURVEILLANCE EXPRESSWAYS

LOCATION	QUANTITY (CAL DAY)
STATION	
JOBSITE	32
TOTAL	32

TEMPORARY PAVEMENT

LOCATION	OFFSET	QUANTITY (SQ YD)
STATION		
STA. 16+05 TO STA. 16+53	LT	34.0
STA. 23+53 TO STA. 24+50	LT	61.2
STA. 15+04 TO STA. 16+51	RT	231.2
STA. 23+60 TO STA. 23+81	RT	10.8
STA. 10+25 TO STA. 17+50	LT/RT	403.0
STA. 22+50 TO STA. 35+34	LT/RT	976.0
TOTAL		1716.2

FLEXIBLE DELINEATORS

LOCATION	QUANTITY (EACH)
*JOBSITE	80
TOTAL	80

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

LOCATION	QUANTITY (EACH)
PRESTAGE	2
STAGE I	4
IL 394	4
TOTAL	10

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3

LOCATION	QUANTITY (EACH)
STAGE II	4
TOTAL	4



*ESTIMATED QUANTITY