

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000						CODE NO	ITEM		UNIT				
42101300	PROTECTIVE COAT	SO YD	2818	2818													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200													
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	2383	2383													
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	198	198													
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	192	192													
44213200	SAW CUTS	FOOT	14360	14360													
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10													
*78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	175	175													
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	4160	4160													
*78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	300	300													
*78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	75	75													
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	52	52													
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	100	100													
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	334.1	334.1													
Z0017202	DOWEL BARS 1 1/2"	EACH	8142	8142													
Z0075330	TIE BARS 1 1/4"	EACH	4675	4675													

* SPECIALTY ITEM

FILE NAME =	USER NAME = wjgroendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
g:\pw\work\PIWIDOT\WILGREENDP\012504\Designdgn		DRAWN -	REVISED -			VAR.	2009-059PCC-PP	COOK	18	3	
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 60H50					
PLOT DATE = 5/18/2009		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO