F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	31	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

*(1818, 1919, 1919.15) I-12 62984

	CODE NO.	ITEM	UNIT	QUANTITY	100% STATE URBAN ROADWAY J000-2A
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	222	222
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	160	160
	20200100	EARTH EXCAVATION	CU YD	283	283
	21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	167	167
	25000210	SEEDING, CLASS 2A	ACRE	0.04	0.04
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4
	25100630	EROSION CONTROL BLANKET	SQ YD	167	167
	28000510	INLET FILTERS	EACH	27	27
	42001300	PROTECTIVE COAT	SQ YD	136	136
	44004250	PAVED SHOULDER REMOVAL	SQ YD	264	264
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4	4
	60618324	CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	SQ FT	132	132
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1
	63200310	GUARDRAIL REMOVAL	FOOT	65.5	65.5
	66400550	CHAIN LINK FENCE, 4' (SPECIAL)	FOOT	1,425	1,425
	66410300	CHAIN LINK FENCE REMOVAL	FOOT	1,394	1,394
	67100100	MOBILIZATION	L SUM	1	1
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4
*	~~81000600~~	~~CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL~~	~~FOOT~~	~~10~~	~~10~~
△ *	~~81200120~~	~~CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL~~	~~FOOT~~	~~5~~	~~5~~
*	~~81900200~~	~~TRENCH AND BACKFILL FOR ELECTRICAL WORK~~	~~FOOT~~	~~10~~	~~10~~
*	~~87301125~~	~~ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 3C~~	~~FOOT~~	~~145~~	~~145~~
*	~~89503300~~	~~REMOVE ELECTRIC CABLE FROM CONDUIT~~	~~FOOT~~	~~150~~	~~150~~
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26
	X0324640	FLUTED KNEEWALL	FOOT	1,426	1,426
*	X0324700	WALL MOUNTED SIGN SUPPORT FOR TYPE I PANEL (SPECIAL)	EACH	7	7
	X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	1,089	1,089
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
△	X0326391	IMPACT ATTENUATORS (FULLY REDIRECTIVE, ~~NARROW~~ RESETTABLE) △, TEST LEVEL 2	EACH	1	1
*	X0326312	TRAFFIC SIGNAL POST, PAINTED STEEL (SPECIAL) (7 FT.)	EACH	1	1

△ Rev. 7-21-09

*Specialty Items

AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
71ST ST TO 63RD ST (SOUTHBOUND KNEE WALLS)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: JANUARY 14, 2009 CHECKED BY: RMG

C:\Documents and Settings\mann\Desktop\Dan Ryan P40468.27b squdgn 1/13/2009 2:33:07 PM