



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 21, 2009

SUBJECT: FAU Route 1503 (Indian Trail Road)  
Project M-HPP-4085(007)  
Section 08-00260-01-PV (Aurora)  
Kane County  
Contract No. 63095  
Item 084  
Addendum A  
July 31, 2009 Letting

## TO PROSPECTIVE BIDDERS:

To clarify information it is necessary to revise the following:

### PLANS

Replace existing sheet 11 with the revised sheet 11 dated July 20, 2009.

### PROPOSAL

Replace existing pages 4 and 5 with the attached revised pages 4 and 5.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are printed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,


Eric Harm  
Interim Engineer of Design  
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

## 2. ROADWAY, DRIVEWAY, BIKEPATH AND SIDEWALK

### Earth Excavation

 This item shall be completed in accordance with the applicable portions of Section 202 of the Standard Specifications with the following general additions. This work shall include removal of all earth material shown on the cross sections or as directed by the Engineer. Earth Excavation will also include all aggregate base, sub-base and surface courses. Earth excavation will also include the removal of the aggregate base course used in the temporary pavement. Earth excavation will not include the excavation of topsoil, unsuitable materials, and removal items for existing bituminous and concrete pavements, driveways, bike path, or curb and gutter.

**For this project, it is the intention of this specification to pay for the handling of earthwork material only once, regardless of staging or Contractor's operations.** The Contractor shall be responsible for his earthwork operations for excavating and stockpile excavated materials for re-handling at a later date. This applies to all excavated material to be used in embankments, shoulders or as topsoil re-spread.

Temporary earth stockpiles will not be allowed on the adjacent properties without the permission of the owner and approval of the City. It will be the contractor's responsibility to acquire permission from the appropriate owner prior to stock piling any materials on those properties. The contractor will provide the City with a written statement from the property owner stating said permission has been granted. This work will be considered part of the contract. As such, if the Contractor chooses to do this work as part of the close out or punch list work, contract days will continue to be counted until all stockpiles are removed and all disturbed areas are restored to at least to their original condition.


A shrinkage Factor of 15% was used for this Project.

Overhaul will not be paid for separately but shall be included in the unit price per cubic yard for EARTH EXCAVATION.

### Stage 1A Earthwork

Shoulder and structural embankment constructed in Stage 1A for the temporary pavement required to be removed for the construction Stage 1 and 2 improvements has been calculated and is included in the earth excavation quantities for Stage 1 and 2.

### Furnished Excavation

 Description: This item shall be completed in accordance with the applicable portions of Section 204 of the Standard Specifications. The quantities shown in the plans for Furnish Excavation is the quantity required for the construction of the embankment for the temporary pavement to be constructed in Stage 1A only.





Basis of Payment. This work shall be paid for at the contract unit price per cubic yard for FURNISHED EXCAVATION.

**Removal and Disposal of Unsuitable Material**

Description: This item shall be completed in accordance with the applicable portions of Section 202 of the Standard Specifications with the following general additions. This work will include excavation, stockpiling, or removing of undercut material shown on the cross sections or as directed by the Engineer.

Unstable materials not suitable for embankments or unsuitable materials consisting of debris, concrete, stone, trees, shrubbery or mulch, building materials, contaminated dirt, or other non-organic material will not be permit within the project limits and shall be disposed of off County right-of-way per the Standard Specifications.

Unstable or Unsuitable materials that have a soil classification that is acceptable for use in the type of embankment specified, but are considered unstable only because the insitu-moisture content of the soil is either to high or to low, will not be considered as unstable or unsuitable material. If these soils are needed for use in the formation of the proposed embankments, the soil will be worked or conditioned by discing, tilling, or adding a soil additive to bring the material to optimum moisture content. Moisture content and compaction requirements for embankments will be as specified in Section 205.05 of the Standard Specifications.

In cut sections, the final subgrade shall be prepared as specified in Section 301. In areas where undercuts have been called out on the plans, the final subgrade will be prepared as specified in Section 301 and the subgrade will then be proof rolled. Final determination of the undercut area will be based on the proof roll after the subgrade has been prepared.

It is the intention of this specification to pay for the handling earthwork material only once, except as directed herein and/or approved for additional payment in advance by the Engineer. In the event the Contractor elects to excavate and stockpile any excavated materials for re-handling at a later date, he shall do at his own expense.

Basis of Payment. This work shall be paid for at the contract unit price per cubic yard for REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.

