

SCHEDULE OF QUANTITIES - SEWER PIPE														
PAY ITEM CODE	* * * *				* * * *									
	550B0320	550B0340	55022800	XX005595	XX007754									
UNDERGROUND INFO					PROPOSED PAY ITEM									
SHEET	UPSTREAM STRUCTURE # or (STATION)	UPSTREAM DEPTH	DOWNSTREAM STRUCTURE # or (STATION)	DOWNSTREAM DEPTH	AVERAGE DEPTH	8" PVC STORM	12" PVC COMBINATION	60" RCP IN TRENCH RELIEF	TRENCH BACKFILL CA-6, CY	TRENCH BACKFILL CA-11, CY	60" RCP IN TUNNEL RELIEF	120" RCP IN TRENCH RELIEF	12" PVC IN CASING PIPE COMBINATION	
22	(6147)	8.80	6152	8.80	8.8		5		6.0	0.6				
22	6152	8.80	(6236)	9.20	9.0		84		100.5	9.2				
22	(6147)	16.00	6153	16.00	16.0			6	20.3	3.5				
22	6153	16.00	(6237)	16.00	16.0			85	288.1	50.0				
22	(6236)	0.00	(6396)	0.00	0.0				0.0	0.0			160	
22	(6237)	0.00	(6397)	0.00	0.0				0.0	0.0	160			
22	(6396)	10.00	6479	8.10	9.1		83		96.6	9.1				
22	(6397)	15.80	6486	16.00	15.9			89	301.6	52.3				
22	6479	8.20	6558	6.90	7.6		80		75.1	8.8				
22	6486	16.00	(6519)	16.00	16.0			32	108.4	18.8				
22	(6519)	15.80	(7125)	16.00	15.9			11	37.3	6.5				
22	6558	6.90	(6563)	6.90	6.9		5		4.7	0.6				
22	(7125)	15.80	(7135)	16.00	15.9			10	33.9	5.9				
24	(7135)	0.00	(8250)	0.00	0.0				0.0	0.0	1115			
25	(8250)	16.00	8257	16.00	16.0			7	23.7	4.1				
25	8257	16.00	(8271)	16.00	16.0			14	47.4	8.2				
25	(8271)	16.00	(8305)	16.00	16.0			47	159.3	27.6				
25	(8278)	5.24	(8260)	5.52	5.4	28			18.1	2.2				
25	(9124)	19.00	(9291)	19.00	19.0				711.4	237.8		167		
22	ACCESS AND AUGER PITTS								210.0	0.0				
<b>TOTALS</b>						<b>28</b>	<b>257</b>	<b>301</b>	<b>2,242</b>	<b>445</b>	<b>1,275</b>	<b>167</b>	<b>160</b>	

SCHEDULE OF QUANTITIES - ROADWAY REMOVAL						
STATION	20100110	40600982	44001900	44004400	44004700	XX005314
	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	PAVEMENT REMOVAL (SPECIAL)	SIDEWALK REMOVAL (SPECIAL)	BITUMINOUS DRIVEWAY REMOVAL
	UNIT	SQ YD	FOOT	SQ YD	SQ FT	SQ YD
61+40.00 TO 66+00	0	205	335	601	0	15
71+00 TO 76+50	0	0	0	0	0	0
76+50 TO 82+50	0	0	0	0	0	0
82+50 TO 93+00	14	144	250	222	921	0
<b>TOTAL</b>	<b>14</b>	<b>349</b>	<b>585</b>	<b>823</b>	<b>921</b>	<b>15</b>

SCHEDULE OF QUANTITIES - BITUMINOUS PAVEMENT						
STATION	21001000	31101000	40600100	40600300	40701921	XX000405
	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SUB-BASE GRANULAR MATERIAL, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 12"	BUTT JOINTS, SPECIAL
	SQ YD	TON	GALLON	TON	SQ YD	SQ YD
61+40.00 TO 66+00	644	168	252	1	560	205
71+00 TO 76+50	0	0	0	0	0	0
76+50 TO 82+50	0	0	0	0	0	0
82+50 TO 93+00	161	42	63	0	140	144
<b>TOTAL</b>	<b>805</b>	<b>210</b>	<b>315</b>	<b>1</b>	<b>700</b>	<b>349</b>

SCHEDULE OF QUANTITIES - SIDEWALKS AND CURBS				
STATION	42400200	60603800	60604400	XX007729
	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	DETECTABLE WARNING, SPECIAL
	SQ FT	FOOT	FOOT	SQ FT
61+40.00 TO 66+00	0	325	0	0
71+00 TO 76+50	0	0	0	0
76+50 TO 82+50	0	0	0	0
82+50 TO 93+00	893	35	195	16
<b>TOTAL</b>	<b>893</b>	<b>360</b>	<b>195</b>	<b>16</b>

SCHEDULE OF QUANTITIES - STRUCTURES										
PAY ITEM CODE	* * * *				* * * *					
	60201330	60218400	60233500	60500040						
STRUCTURE INFO					PAY ITEM					
SHEET	STR. NO.	STATION	OFFSET	BASE LINE	CB TY A TY 23 F&G	MH TY A TY 1 F&CL	PRCST "T" MH FOR 60" F&CL	MH REMOVE		
22	6152	61+52.00	10.80'L	6		1				
22	6153	61+52.00	20.00'L	6			1			
22	6479	64+79.30	8.20'L	6		1				
22	6486	64+86.00	17.70'L	6			1			
22	6489	64+89.00	4.50'R	6				1		
22	6558	65+58.00	4.50'R	6		1				
25	8257	82+57.00	4.00'L	7			1			
25	9147	91+47.00	15.00'R	8	1					
<b>TOTALS</b>					<b>7</b>	<b>1</b>	<b>3</b>	<b>3</b>	<b>1</b>	

ALLEYS AND DRIVEWAYS		
STATION	XX007357	X4420132
	CLASS C PATCHES, SPECIAL	CLASS D PATCHES, SPECIAL
	SQ YD	SQ YD
61+40.00 TO 66+00	0	15
71+00 TO 76+50	0	0
76+50 TO 82+50	0	0
82+50 TO 93+00	85	0
<b>TOTAL</b>	<b>85</b>	<b>15</b>

REVISIONS	
NAME	DATE

\* = DENOTES SPECIALTY ITEM

PLAN SURVEYED BY DATE  
 CHECKED BY DATE  
 NOTE BOOK NO. FILE NAME

PROFILE SURVEYED BY DATE  
 CHECKED BY DATE  
 NOTE BOOK NO. STRUCTURE NOTATIONS CPFD