ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 347	06-000071-00-SW	COOK	17	3
ILLINOIS PROJECT	TE-00D1(773)			
VILLAGE SECTION				
CONTRACT NO. 63183				

SUMMARY OF QUANTITIES

	CODE	PAY ITEM	UNIT	SFTY-1B 80% FEDERAL 20% LOCAL
	20200100	EARTH EXCAVATION	CUYD	105
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	500
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6
	25200110	SODDING, SALT TOLERANT	SQYD	500
	25200200	SUPPLEMENTAL WATERING	UNIT	5
	42101300	PROTECTIVE COAT	SQYD	1,340
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQFT	12,000
✪	42400800	DETECTABLE WARNINGS	SQFT	108
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	120
	44000600	SIDEWALK REMOVAL	SQFT	12,000
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5
✪	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5
✪	60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	120
	67100100	MOBILIZATION	L SUM	1
✪	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1
★✪	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
★✪	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
★	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	411
★	81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	90
★	81603040	UNIT DUCT, 600V, 2-1/C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA., POLYETHYLENE	FOOT	2,200
★	81702400	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 3-1/C NO. 2	FOOT	125
★✪	82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1
★	83600300	LIGHT POLE FOUNDATION, 30" DIA.	FOOT	78
★✪	XX001399	UNIT DUCT, BORED AND PULLED	FOOT	1,750
✪	XX003059	DECORATIVE BRICK SIDEWALK	SQFT	3,100
✪	XX005644	MINOR SIGN COMPLETE	EACH	1
★✪	XX006937	GROUND ROD, 5/8" X 10 FT	EACH	14
✪	XX007000	PORTLAND CEMENT CONCRETE BASE COURSE, 3"	SQFT	3,100
✪	X0324062	ENTRANCE SIGN	L SUM	1
★✪	X8210415	LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, POST MOUNT, 100 WATT	EACH	13
★✪	XX008103	LIGHT POLE, CONCRETE 16 FT. MOUNTING HEIGHT	EACH	13
✪	XX008104	POLE MOUNTED PLANTER BASKET	EACH	13
✪	XX008105	INCIDENTAL HOT-MIX ASPHALT SURFACING	SQYD	20

★ DENOTES SPECIALTY ITEM

✪ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

REVISION:

HANCOCK ENGINEERING
- Civil Engineers
- Municipal Consultants
- Established 1911

9933 Roosevelt Road
Westchester, Illinois 60154-2780
Phone: 708/865-0390
Fax: 708/865-0212

VILLAGE OF WESTCHESTER
ROOSEVELT ROAD (FAP 347)
BEAUTIFICATION PROJECT
SUMMARY OF QUANTITIES

DRAWN BY: MK
CHECKED BY: JCG
SCALE: NONE
DATE: 04/15/09

E.H.E. PROJECT NO. : 838-06-26320

Drawing file: W:\Projects\63656263 - Roosevelt Rd ITEP\Summary.dwg May 27, 2009 - 1:59pm