

CONTRACT NO. 63204



CHESTER AVENUE
CONTRACT BEGINS
AT STA. 0+35

CHESTER AVENUE
CONTRACT OMISSION
STA. 5+33
TO 5+99

FOR CONTINUATION
SEE SHEET 5
67th STREET

FOR CONTINUATION
SEE SHEET 4
COBB STREET

FOR CONTINUATION
SEE SHEET 4
LYONS STREET

WENZ AVENUE
CONTRACT BEGINS
AT STA. 0+35

WENZ AVENUE
CONTRACT OMISSION
STA. 5+33
TO 5+99

FOR CONTINUATION
SEE SHEET 5
67th STREET

FOR CONTINUATION
SEE SHEET 4
COBB STREET

FOR CONTINUATION
SEE SHEET 4
LYONS STREET

CONRAD AVENUE
CONTRACT BEGINS
AT STA. 0+38

CONRAD AVENUE
CONTRACT OMISSION
STA. 5+24
TO 6+01

FOR CONTINUATION
SEE SHEET 5
67th STREET

FOR CONTINUATION
SEE SHEET 4
COBB STREET

CONRAD AVENUE
CONTRACT ENDS
AT STA. 10+79

FOR CONTINUATION
SEE SHEET 4
LYONS STREET

FOR CONTINUATION
SEE SHEET 5

FOR CONTINUATION
SEE SHEET 4

FOR CONTINUATION
SEE SHEET 4

NOTE:
FOR CONTINUATION OF NORTH-SOUTH
STREETS TO BE RESURFACED, SEE SHEET 5

NOTE:
1) ALL SAW CUTS SHALL BE CONSIDERED INCIDENTAL
TO THE CONTRACT

- LEGEND**
- DENOTES HOT-MIX ASPHALT SURFACE REMOVAL (SEE SHEET 3 FOR SCOPE OF WORK)
 - DENOTES HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT (4.5' WIDTH) WITH 15' TAPER LENGTH
 - DENOTES DRIVEWAY PAVEMENT REMOVAL AND INCIDENTAL HOT-MIX ASPHALT SURFACING, 3"
 - DENOTES CLASS D PATCHES, TYPE I-IV, 8", - AS DIRECTED
 - DENOTES PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT, 7"
 - DENOTES PAVEMENT REMOVAL AND P.C. CONCRETE PAVEMENT, 8"
 - DENOTES P.C. CONCRETE SIDEWALK, 5" REMOVAL & REPLACEMENT, WITH DETECTABLE WARNING TACTILE STRIP FOR HANDICAP RAMPS PER I.D.O.T. STANDARD 424001-05
 - "A"** DENOTES EXISTING VALVE VAULTS, VALVE BOXES, INLETS, CATCH BASINS AND MANHOLES TO BE CLEANED, GROUTED, AND ADJUSTED TO GRADE WITH NEW ADJUSTING RINGS. (ALL TOP BANDS OF FALLEN, COMMON OR CONCRETE BRICK TO BE REPLACED WITH PRECAST CONCRETE ADJUSTING RINGS)
 - "S"** DENOTES EXISTING STRUCTURES TO BE ADJUSTED (SPECIAL) (SEE SHEET 12 FOR DETAIL)
 - DENOTES COMBINATION CONCRETE CURB & GUTTER REMOVAL AND REPLACEMENT PROVIDE DETECTABLE WARNINGS AND RAMPS AT ALL SIDEWALK
 - DENOTES EXISTING SIDEWALK RAMP TO REMAIN

FOR TYPICAL CROSS SECTION OF NEW PAVEMENT WORK
SEE SHEET 3

IMPORTANT!
FULL SIZE PLANS HAVE BEEN
PREPARED USING STANDARD
ENGINEERING SCALES. REDUCED
SIZED PLANS WILL NOT CONFORM
TO STANDARD SCALES INDICATED
IN TITLE BLOCK.

Frank Novotny & Associates, Inc.
Civil Engineers/
Municipal Consultants
825 Midway Drive • Willowbrook, IL • 60527 • Telephone: (630) 887-8640 • Fax: (630) 887-0132
Illinois Professional Design Firm No. 184-000928

PROJECT
VILLAGE OF HODGKINS, ILLINOIS
LAPP STREET RESURFACING
MFT SECTION NO. 09-00016-00-RS

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PLAN:
CHESTER AVENUE - 67th ST. TO LYONS ST.
WENZ AVENUE - 67th ST. TO LYONS ST.
CONRAD AVENUE - 67th ST. TO LYONS ST.

PROJECT NO. 09055	SCALE 1"=40'	SHEET 6 OF 18 SHEETS
DRAWN/DESIGNED JFP/JLC	DATE APR., 2009	
CHECKED/APPROVED JLC	FIELD BOOK NO. FILE	

(RESURFACING)