

**SUMMARY OF QUANTITIES**

SPECIALTY ITEM	CODE NUMBER	PAY ITEM DESCRIPTION	UNITS	ROADWAY 100% FEDERAL 1000
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,055
	40600300	AGGREGATE (PRIME COAT)	TON	45
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,235
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	920
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,430
	42400800	DETECTABLE WARNINGS	SQ FT	120
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	21,540
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300
	44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	625
	44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	60
	44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	220
	44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	220
	44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	60
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	200
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	3
	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8
	67100100	MOBILIZATION	L SUM	1
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,860
	70300200	TEMPORARY PAVEMENT MARKING	FOOT	720
*	78000100	THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	410
*	78000200	THERMOPLASTIC PAVEMENT MARKING, LINE 4 INCH	FOOT	14,050
*	78000400	THERMOPLASTIC PAVEMENT MARKING, LINE 6 INCH	FOOT	1,280
*	78000600	THERMOPLASTIC PAVEMENT MARKING, LINE 12 INCH	FOOT	320
*	78000650	THERMOPLASTIC PAVEMENT MARKING, LINE 24 INCH	FOOT	210
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	200
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	280
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	200
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	100
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	170
	X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	50

COMPANY NAME: Smith  
 PROJECT CONTACT: CHAUDHRY  
 CLIENT: VILLAGE OF STREAMWOOD  
 DATE PLOTTED: 5/26/2009 11:56:12 AM  
 FILE NAME: 090118-sum-01.dgn  
 PLOT DRIVER: pdfLDT  
 PEN TABLE: standard-trans.tbl



USER NAME = charlke	DESIGNED - C. HARTKE	REVISED -
	DRAWN - J. ATTANASEO	REVISED -
PLOT SCALE =	CHECKED - T. HAMILTON	REVISED -
PLOT DATE = 5/26/2009	DATE - 5/22/09	REVISED -

**VILLAGE OF STREAMWOOD**

**SUMMARY OF QUANTITIES**

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.U. RTE. 1321	SECTION 09-00053-00-RS	COUNTY COOK	TOTAL SHEETS 13	SHEET NO. 3
			CONTRACT NO. 63213				
			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT ARA-9003(304)				