



**NOTES:**

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

COMPANY NAME: SMITH CONSULTING  
 PROJECT CONTACT: VILLAGES OF STREAMWOOD  
 DATE PLOTTED: 5/26/2009 11:58:54 AM  
 FILE NAME: 090118-ar-08.dgn  
 PLOT DRIVER: pdf.plt  
 PEN TABLE: standard-trans.tbl

**SEC Group, Inc.**  
 Illinois Professional Geograph Firm # 104-000108  
 Engineering  
 Surveying  
 Planning  
 Landscape Architecture  
 McHenry • Yorkville • New Lenox • Chicago  
 www.secgroupinc.com

USER NAME = char-uke	DESIGNED -	REVISED - R. MIRS 09-15-97
	DRAWN -	REVISED - R. MIRS 12-11-97
PLOT SCALE =	CHECKED -	REVISED - T. RAMMACHER 02-02-99
PLOT DATE = 5/26/2009	DATE - 5/22/09	REVISED - C. JUCIUS 01-31-07

**VILLAGES OF STREAMWOOD**

**ARTERIAL ROAD  
INFORMATION SIGN**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	09-00053-00-RS	COOK	13	12
<b>TC-22</b>			CONTRACT NO. 63213	
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	ARA-9003(304)		