

SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

LOCATION	OFFSET (FT.)	UNIT
STA 1113 +21.00	40' LT	9
STA 1113 +21.00	40' LT	10
STA 1113 +21.00	40' LT	8
STA 1113 +21.00	40' LT	7
STA 1113 + 44.21	46' LT	6
STA 1113 + 55.21	37' LT	6
STA 1113 + 68.04	35' LT	6
STA 1113 + 68.04	35' LT	6
STA 1113 +70.59	55 LT'	12
STA 1113 + 93.20	38' LT	6
STA 1113 + 98.65	37' LT	8
STA 1114 +07.15	50' LT	7
STA 1114 + 11.11	49' LT	6
STA 1114 + 15.83	40' LT	7
STA 1114 + 15.83	40' LT	6
STA 1114 + 27.03	41' LT	8
STA 1114 + 27.77	45' LT	7
STA 1114 + 27.77	45' LT	6
STA 1114 + 27.77	45' LT	6
STA 1114 + 29.27	35' RT	10
STA 1114 + 29.27	35' RT	7
STA 1115 + 55.61	34' RT	6
STA 1115 + 55.61	34' RT	6
STA 1115 + 96.84	37' RT	6
STA 1116 + 50.08	36' RT	6
STA 1116 + 50.08	36' RT	6
STA 1116 + 80.07	37' RT	6
STA 1116 + 80.07	37' RT	9
STA 1116 + 91.37	40' RT	8
STA 1116 + 95.49	39' RT	6
STA 1116 + 96.53	35' RT	6
STA 1117 + 06.21	39' RT	6
TOTAL		225

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

LOCATION	OFFSET (FT.)	UNIT
STA 1114 + 27.03	41' LT	16
STA 1114 + 27.03	41' LT	20
STA 1114 + 59.54	101' RT	16
STA 1116 + 90.20	29' RT	41
TOTAL		93

20400800 FURNISHED EXCAVATION

LOCATION	CU YD
STA 1111 + 50 TO STA 1118 + 75.55	815
TOTAL	815

21101615 TOPSOIL FURNISH AND PLACE, 4"

LOCATION	SQ YD
STA 1111 + 50 TO STA 1118 + 75.55 LT	2904
STA 1111 + 50 TO STA 1118 + 75.55 RT	1936
TOTAL	4840

25000210 SEEDING, CLASS 2A

LOCATION	ACRE
STA 1111 + 50 TO STA 1118 + 75.55 LT	0.35
STA 1111 + 50 TO STA 1118 + 75.55 RT	0.40
TOTAL	0.75

25000310 SEEDING, CLASS 4

LOCATION	ACRE
STA 1111 + 50 TO STA 1118 + 75.55 LT	0.25
TOTAL	0.25

25000750 MOWING

LOCATION	ACRE
STA 1111 + 50 TO STA 1118 + 75.55 LT	0.6
STA 1111 + 50 TO STA 1118 + 75.55 RT	0.4
TOTAL	1.0

25100115 MULCH, METHOD 2

LOCATION	ACRE
STA 1111 + 50 TO STA 1118 + 75.55 LT	0.6
STA 1111 + 50 TO STA 1118 + 75.55 RT	0.4
TOTAL	1.0

25100630 EROSION CONTROL BLANKET

LOCATION	SQ YD
STA 1111 + 50 TO STA 1118 + 75.55 LT	2904
STA 1111 + 50 TO STA 1118 + 75.55 RT	1936
TOTAL	4840