SCHEDULE OF QUANTITIES

28000250 TEMPORARY EROSION CONTROL SEEDING

LOCATION				POUND
STA 1111 + 50	TO	STA 1118 + 75.55	LT	60
STA 1111 + 50	TO	STA 1118 + 75.55	RT	40
			TOTAL	100

28000300 TEMPORARY DITCH CHECKS

LOCATION				EACH
STA 1111 + 50	TO	STA 1118 + 75.55	LT	17
			TOTAL	17

28000400 PERIMETER EROSION BARRIER

LOCATION				FOOT
STA 1111 + 50	TO	STA 1118 + 75.55	RT	790
			TOTAL	790

28000500 INLET AND PIPE PROTECTION

LOCATION			EACH
STA 1114 + 24.84	LT		1
STA 1114 + 36.11	LT		1
		TOTAL	2

28100107 STONE RIPRAP, CLASS A4

LOCATION			SQ YD
STA 1114 + 30.48	RT		100
		TOTAL	100

28200200 FILTER FABRIC

LOCATION			SQ YD
STA 1114 + 30.48	RT		100
		TOTAL	100

40603335 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50

LOCATION			TON
STA 1113 + 99.29	TO	STA 1114 + 61.74	26
		TOTAL	26

44201433 CLASS C PATCHES, TYPE IV, 16 INCH

LOCATION			SQ YD
STA 1113 + 99.29	TO	STA 1114 + 61.74	182
		TOTAL	182

48101200 AGGREGATE SHOULDERS, TYPE B

LOCATION				TON	REMARKS
STA 1111 + 50	TO	STA 1118 + 75.55	LT	290	
STA 1111 + 50	TO	STA 1118 + 75.55	RT	290	
STA 1111 + 50	TO	STA 1118 + 75.55	LT	145	STAGE I - TRAFFIC CONTROL
STA 1111 + 50	TO	STA 1118 + 75.55	RT	145	STAGE II - TRAFFIC CONTROL
			TOTAL	870	

50100100 REMOVAL OF EXISTING STRUCTURES

LOCATION		EACH
STA 1114 + 30.48		1
	TOTAL	1

51500100 NAME PLATES

LOCATION		EACH	REMARKS
STA 1114 + 30.48		1	NEW SN 071- 1229
	TOTAL	1	

54200499 PIPE CULVERTS, TYPE 1 RCCP 84"

LOCATION		FOOT
STA 1114 + 24.84		84
STA 1114 + 36.11		84
	TOTAL	168

54213729 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 84"

LOCATION			EACH
STA 1114 + 24.84	LT		1
STA 1114 + 24.84	RT		1
STA 1114 + 36.11	LT		1
STA 1114 + 36.11	RT		1
		TOTAL	4

5422D048 PIPE CULVERTS, CLASS D, TYPE 2 48" (TEMPORARY)

LOCATION			FOOT
STA 1114 + 24.84	RT		32
STA 1114 + 36.11	RT		32
		TOTAL	64

63200310 GUARDRAIL REMOVAL

LOCATION				FOOT
STA 1112 + 67.20	TO	STA 1115 + 57.50	RT	291
STA 1112 + 93.03	TO	STA 1115 + 95.70	LT	303
			TOTAL	594