

SCHEDULE OF QUANTITIES

63500105 DELINEATORS

<u>LOCATION</u>	<u>EACH</u>
STA 1114 + 24.84 LT	1
STA 1114 + 24.84 RT	1
STA 1114 + 36.11 LT	1
STA 1114 + 36.11 RT	1

TOTAL 4

78001110 PAINT PAVEMENT MARKING - LINE 4"

<u>LOCATION</u>	<u>FOOT</u>	<u>REMARKS</u>
STA 1111 + 50 TO STA 1118 + 75.55	182	YELLOW SKIP DASH
STA 1113 + 19.15 TO STA 1118 + 75.55 RT	557	NO PASSING ZONE
STA 1111 + 50 TO STA 1118 + 75.55 LT	726	WHITE EDGE LINE
STA 1111 + 50 TO STA 1118 + 75.55 RT	726	WHITE EDGE LINE

TOTAL 2191
TOTAL 4382 2 APPLICATIONS

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

<u>LOCATION</u>	<u>OFFSET (FT.)</u>	<u>EACH</u>
STA 1111 + 00.00	40' RT	1
STA 1112 + 00.00	50' RT	1
STA 1113 + 75.00	50' RT	1
STA 1114 + 25.00	100' RT	1
STA 1114 + 75.00	100' RT	1
STA 1115 + 25.00	60' RT	1
STA 1116 + 50.00	60' RT	1
STA 1117 + 25.00	65' RT	1
STA 1118 + 77.24	64.04' RT	1

TOTAL 9

X0322118 REMOVE CONCRETE FLARED END SECTIONS

<u>LOCATION</u>	<u>EACH</u>
STA 1117 + 03.15 LT	1
STA 1117 + 03.15 RT	1

TOTAL 2

X4420500 TEMPORARY PAVEMENT PATCH

<u>LOCATION</u>	<u>SQ_YD</u>	<u>REMARKS</u>
STA 1112 + 49.29 TO STA 1116 + 11.74	521	STAGE I TRAFFIC
STA 1113 + 99.29 TO STA 1114 + 61.74	201	STAGE I - MAINLINE
STA 1112 + 49.29 TO STA 1116 + 11.74	1441	STAGE II TRAFFIC
STA 1113 + 99.29 TO STA 1114 + 61.74	603	STAGE II - MAINLINE

TOTAL 2766

66700305 PERMANENT SURVEY MARKERS, TYPE II

<u>LOCATION</u>	<u>EACH</u>
STA 1111 + 50 TO STA 1118 + 75.55	2

TOTAL 2

Z0023600 FILLING EXISTING CULVERTS

<u>LOCATION</u>	<u>EACH</u>
STA 1117 + 03.15	1

TOTAL 1

70300100 SHORT-TERM PAVEMENT MARKING

<u>LOCATION</u>	<u>FOOT</u>	<u>REMARKS</u>
STA 1111 + 50 TO STA 1118 + 75.55	1452	NO PASSING ZONE

TOTAL 1452

Z0025500 FURNISHING AND INSTALLING PROPERTY MARKERS

<u>LOCATION</u>	<u>OFFSET (FT.)</u>	<u>EACH</u>
STA 1114 + 31.77	100' RT	1

TOTAL 1

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

<u>LOCATION</u>	<u>FOOT</u>
STA 1111 + 50 TO STA 1118 + 75.55	484

TOTAL 484