

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X071-2A 20% STATE 80% FED			CODE NO	ITEM	UNIT		X071-2A 20% STATE 80% FED		
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		X7200200	WIDE LOAD SIGNING	L SUM	1	1			
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3		Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	2			
*63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1		Z0030360	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	2	2			
63200310	GUARDRAIL REMOVAL	FOOT	788	788		X0325445	RIGHT-OF-WAY AND PROPERTY CORNERS	EACH	1	1			
66500105	WOVEN WIRE FENCE, 4'	FOOT	638	638		Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22	22			
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	598	598									
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8	8									
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2	2									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9									
67100100	MOBILIZATION	L SUM	1	1									
70100400	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1									
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1									
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	2	2									
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1									
70106700	TEMPORARY RUMBLE STRIP	EACH	24	24									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	87	87									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6396	6396									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	21.7	21.7									
70400100	TEMPORARY CONCRETE BARRIER	FOOT	225	225									
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	225	225									
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2928	2928									
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	540	540									
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9									
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2									
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16									
*78200530	BARRIER WALL MARKERS, TYPE C	EACH	8	8									
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4									
78300100	PAVEMENT MARKING REMOVAL	SQ FT	651	651									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	11	11									
X0324840	DISKING	ACRE	0.2	0.2									
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	6	6									

\*SPECIALTY ITEMS

FILE NAME =	USER NAME = manntm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.				
c:\pwork\pwork\manntm\dms51935\p1n02\06.dgn						SCALE:	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	325	3BR-2	JERSEY	90	4
PLOT SCALE = 50.0000' / IN.						CHECKED -	CONTRACT NO. 76B01		FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT					
PLOT DATE = 12/11/2008						DATE -								

Rev