

SUMMARY OF QUANTITIES

URBAN
100% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	J000		
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	5393		
44213100	PAVEMENT FABRIC	SQ YD	5221		
44200628	CLASS A PATCHES, TYPE IV, 14 INCH	SQ YD	5221		
44213000	PATCHING REINFORCEMENT	SQ YD	5221		
44213200	SAW CUTS	FOOT	6693		
60100070	SHOULDER REMOVAL AND REPLACEMENT	FOOT	3761		
60107600	PIPE UNDERDRAINS 4"	FOOT	3761		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		
67100100	MOBILIZATION	L SUM	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1		
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	232		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2876		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	831		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2069		
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	2876		
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	831		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	36		
X0324743	SUBGRADE REINFORCEMENT	SQ YD	5393		
X0324952	DETOUR SIGNING	L SUM	1		
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1		
Z0017202	DOWEL BARS 1 1/2"	EACH	149		
Z0021400	EXPANSION JOINT (SPECIAL)	FOOT	168		
Z0075310	TIE BARS 3/4"	EACH	647		
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1		

* SPECIALTY ITEMS

Rev.