

INDEX OF SHEETS

- 1. COVER SHEET
- 2. INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, AND COMMITMENTS
- 3. SUMMARY OF QUANTITIES
- 4. SCHEDULE OF QUANTITIES
- 5. GENERAL PLAN AND ELEVATION
- 6. STEEL GRID FLOOR - SPAN 10
- 7 - 9. MLK CLOSURE PLAN
- 10. - 11. CONCRETE SAFETY BARRIER
- 12. BARRIER DETAIL AT EXPANSION JOINTS
- 13. MISCELLANEOUS DETAILS
- 14 - 15. PAVEMENT MARKING

STANDARDS

- 000001-05
- 001001-02
- 001006
- 630001-08
- 631033-03
- 701400-03
- 701451
- 704001-05
- 780001-02
- 781001-03

COMMITMENTS

AS PART OF DEVELOPING THIS PROJECT THESE COMMITMENTS WERE MADE:

- 1. INSTALLATION OF 6" PREFORMED PLASTIC TY B PAVEMENT MARKING TAPE - GROOVED IN.
- 2. INSTALL SPEED REDUCTION PAVEMENT MARKING
- 3. INSTALL PARAPET AND BARRIER DELINEATION - LDS STRIPE.
- 4. REMOVE AND REPLACE WITH NEW STANDARD THE GUARDRAIL ON THE MLK DRIVE RAMPS.
- 5. REMOVE THE EXISTING NEW JERSEY BARRIER AND REACT 350 ON THE WEST END OF THE RR APPROACH AND DELIVER TO THE BOWMAN YARD.
- 6. INCLUDE AN ADDITIONAL 10-15% OF THE CONCRETE SAFETY BARRIER FOR IMMEDIATE REPAIR NEEDS TO THE SYSTEM.

GENERAL NOTES

- 1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
- 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- 3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMERENIP
 - AMERENUE
 - AT&T ILLINOIS
 - EXPLORER PIPELINE COMPANY
 - ILLINOIS AMERICAN WATER COMPANY
 - LACLEDE PIPELINE COMPANY
 - LEVEL 3 COMMUNICATIONS, LLC
 - LIGHTCORE
 - MCI NETWORK SERVICES, INC
 - PAETEC/MCLEOD USA TELECOMMUNICATIONS, INC.
 - QUEST SOLUTIONS CENTER
 - SPRINT/NEXTEL

MEMBERS OF J.U.L.I.E (800) 892-0123 ARE INDICATED BY *. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- 4. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING STRUCTURE AND ROADWAY HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
- 5. THE CONTRACTOR SHALL FURNISH AND INSTALL WOOD SIGN SUPPORTS IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS, HOWEVER, INSTALLATION BY METHOD "A" (ARTICLE 730.04(A)) SHALL BE THE ONLY METHOD PERMITTED.
- 6. EXTRA CARE SHALL BE REQUIRED TO REMOVE EXISTING OVERLAY AROUND THE DECK DRAINS AND EXPANSION JOINTS. OVERLAY WITH IN ONE (1) FOOT OF THE DECK DRAINS AND EXPANSION JOINTS SHALL BE REMOVED BY HAND AS DIRECTED BY THE ENGINEER.
- 7. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS CONTRACT:

MIXTURE USE	POLY-SURFACE
AC/PG	SBS PG 76-28
RAP % (MAX)	0%
DESIGN AIR VOIDS	3.5% @ Ndes=70
MIX COMPOSITION	
(GRADATION MIXTURE)	IL 9.5/12.5
FRICTION AGG	MIXTURE "D"