

PAVEMENT MARKING SCHEDULE

STATION							PERFORMED PLASTIC PAVEMENT MKG TYPE B				PAVEMENT MARKING GROOVING (FT)	RAISED REFLECTIVE PVMT MKR (EA)	RAISED REFLECTIVE PVMT MKR (BRIDGE) (EA)	
							6" WHITE LINE (FT)	6" YELLOW LINE (FT)	8" YELLOW LINE (FT)	12" WHITE LINE TYPE B (FT)				
WEST BOUND														
2+00.00	40.92'	LT	TO	53+47.00	26.88 FT	LT	EDGE LINE	5148.22			5148.22			
12+00.00			TO	14+04.00			SPEED REDUCTION PVMT MKG			42.00	42.00			
35+55.50			TO	37+59.50			SPEED REDUCTION PVMT MKG			42.00	42.00			
42+45.00	9.2 FT	LT	TO	35+03.10	10.13 FT	LT	EDGE LINE @ ENTRANCE RAMP	741.90			741.90	5		
41+00.00	8.75 FT	RT	TO	35+03.10	9.0 FT	RT	EDGE LINE @ ENTRANCE RAMP			401.04	401.04	5		
41+00.00	8.75 FT	RT	TO	35+03.10	28.7 FT	RT	EDGE LINE @ ENTRANCE RAMP			396.90	396.90			
2+00.00	7.00'	LT	TO	60+82.70	12.0 FT	LT	EDGE LINE		5883.91		5883.91			
EAST BOUND														
2+00.00	5.75'	RT	TO	60+82.70	7.5 FT	LT	EDGE LINE		5884.69		5884.69			
2+00.00	18.50	RT	TO	3+28.07	7.5 FT	RT	EB CENTER LINE					2		
2+00.00		RT	TO	52+00.00	3.9 FT	RT	SKIP DASH	1259.80			1259.80			
3+28.00	7.5 FT	RT	TO	43+48.75	7.5 FT	RT							50	
5+96.00			TO	8+00.00			SPEED REDUCTION PVMT MKG			84.00	84.00			
28+96.00			TO	29+00.00			SPEED REDUCTION PVMT MKG			84.00	84.00			
43+38.39	7.5 FT	RT	TO	52+00.00	3.9 FT	RT	EB CENTER LINE					11		
52+00.00	3.9 FT	RT	TO	60+82.70	7.9 FT	RT	EDGE LINE @ EXIT RAMP		866.31		866.31	11		
55+20.00	7.5 FT	RT	TO	58+63.5	16.5 FT	RT	CHEVRON			231.66				
52+00.00	3.9 FT	RT	TO	60+82.70	33.5 FT	RT	EDGE LINE @ EXIT RAMP		876.55		876.55	11		
2+00.00		RT	TO	52+28.00	16.75 FT	RT	EDGE LINE	5035.87			5035.87			
0+00.00	8.3 FT	LT	TO	8+42.20	6.0 FT	LT	EDGE LINE @ EXIT RAMP	842.2			842.20			
SUB-TOTAL								13027.99	11768.60	2540.80	483.66	27589.39	44	50
TOTAL								24796.59	2540.80	483.66	27589.39	44	50	

TEMPORARY BARRIER SCHEDULE

LOCATION				TEMPORARY CONCRETE BARRIER (FT)	IMPACT ATTEN., TEMP. (NON RED.), TEST LEVEL 3 (EA)	IMPACT ATTEN., TEMP. (NON RED., NARROW.), TEST LEVEL 3 (EA)
36+32.50	TO	38+56.00	RT WB MLK APPR.	425		
38+56.00			RT WB MLK APPR.		1	
36+53.00	TO	38+57.50	LT RAMP 2	312.5		
38+57.50			LT RAMP 2		1	
I-70 EB MISSOURI				RT MLK RAMP	262.5	1
TOTAL				1000	2	1

RESURFACING SCHEDULE

STATION			RT/LT	POLYMERIZED HMA SURF. CSE., MIX "D", N70 (TON)	WATER PROOFING MEMBRANE SYSTEM (SQ YD)	FILLING EXISTING RUMBLE STRIP (FT)
2+11.50	TO	15+90.42				1378.9
15+90.42	TO	23+13.25	RT/LT	314.83	3212.58	
23+13.25	TO	54+65.99				3152.7
TOTAL				314.83	3212.58	4531.66

CONCRETE BARRIER SCHEDULE

LOCATION		CONCRETE SAFETY BARRIER, SPECIAL (FT)	LINEAR DELINEATION PANELS, 6 IN (EA)
2+00.00	TO 60+19.75	5880.00	2352
ADD 10.31%		600.00	
2+00.00	TO 10+00.00	CONCRETE PARAPET, MO SIDE	256
29+00.00	TO 43+38.50	CONCRETE PARAPET, IL SIDE	460
TOTAL		6480.00	3068

GUARDRAIL SCHEDULE

LOCATION		STEEL PL BEAM GUARDRAIL T-A, 6' POSTS (FT)	TRAFFIC BARRIER TYPE 6B (EA)	GUARDRAIL MARKERS TYPE A (EA)	DELINEATORS (EA)
MLK DRIVE	RAMP B	912.5	2	13	10
MLK DRIVE	RAMP B	AT CURB UNDER STRUCTURE	100	2	2
MLK DRIVE	RAMP C	312.5	2	5	4
TOTAL		1325	4	20	16

REMOVAL SCHEDULE

STATION			PAVEMENT MARKING REMOVAL (SQ FT)	RAISED REFL. PVMT. MKR REMOVAL (EA)	BITUMINOUS CONCRETE REMOVAL (DECK) (SQ YD)	IMPACT ATTENUATOR REMOVAL (EA)	CONCRETE BARRIER REMOVAL (FT)	GUARDRAIL REMOVAL (FT)
2+00.00	TO	15+90.42	EB & WB EDGE LINE	463.5				
2+00.00	TO	15+90.42	EB & WB CL	231.7	35			
2+00.00	TO	15+90.42	CENT. LINE	926.9	35			
15+90.42	TO	23+13.25	STEEL GRID FLOOR			3212.6		
23+13.25	TO	52+28.00	EB EDGE LINE	971.6				
0+00.00	TO	8+41.00	EB EDGE LINE	280.3				
23+13.25	TO	54+00.00	EB CENT LINE	257.2	39			
54+00.00	TO	58+60.00	EB GORE	669.9	12			
23+13.25	TO	59+85.00	CENT. LINE	2447.8	92			
23+13.25	TO	55+68.50	WB CENT LINE	271.3	41			
55+68.50	TO	60+82.70	WB GORE	342.8				
60+00.00						1	69	
MLK DRIVE			RAMPS B & C					
SUB-TOTAL								1500
TOTAL				6863.1	252	3212.6	1*	69*

*SEE COMMITMENTS